GB-21 1989/A1

Department of Veterans Affairs

Standard details
Architectural

Handbook H-08-4
Volume I
March 1989

Office of Facilities
Washington DC 20420

VA 1.10/5:

Department of Veterans Affairs
Washington, DC 20420

H-08-4
January 15, 1989

1. **Material Transmitted.** The attached Architecture Section is reprinted in its entirety as Volume 1 of VA Handbook, H-08-4, "Standard Details."

2. **Effective Date:** This revision is effective immediately.

3. **RESCISSION:** H-08-4, volume I, dated October 3, 1986.

GERALD E. NEUMANN
Director
Office of Facilities

Distribution: RPC: 0831
FD

Department of Veterans Affairs
Washington, DC 20420

H-08-4
January 15, 1989

INTRODUCTION

1. VA Handbook H-08-4, "Standard Details," is a complete set of standard details drawings, Volumes I-IV, to be used for reference purposes on Veterans Administration project.

2. Standard detail drawings are furnished to DM&S field stations for their guidance in the planning and accomplishment of construction projects, minor improvements, and maintenance and repair projects. Specific instructions for field station usage will be prescribed by the Chief Medical Director.

3. All drawings are identified by a title and number; the numbers also serve as page numbers. Drawings are grouped in four sections as follows:

Architecture, Vol. I, 1-199
Site Engineering, and Landscaping Vol. II, 200-299
Mechanical Engineering, Vol. III
  Section I, Plumbing & Sanitary, 300-599
  Section II, Heating, Ventilating & Air Conditioning, 600-699
  Section III, Steam Generation and Outside Steam Distribution, 700-799
Electrical Engineering, Vol. IV, 800-899

4. Throughout the handbook there are gaps in the sequence of detail numbers. Generally these missing numbers are reserved for future revision or expansion of the series.

5. For ease of reference the index is arranged by subject in alphabetical order. As appropriate, the index will be reissued to include new and revised standard details. New and revised drawings will be issued with a transmittal sheet.

6. Field stations may request specific additional pages directly from the Chief, Administrative Services Division (082C), Office of Facilities.

GERALD E. NEUMANN, Director
Office of Facilities

Distribution: RPC: 0831
FD

STANDARD DETAILS INDEX

Architectural
As of January 1989

A

Abbreviations (Architectural) 1A
Access Door (Wire Mesh) & Ladder 34
Agent Cashier Service
  Windows & Doors 67
Ambulance Entrance Details
  For Head-in or Drive Thru Unloading 58
Ambulance Entrance Details For
  Back-in Unloading 59
Anchorage for Wall Mounted Items 66
Architectural Symbols 1, 1.1, 1.2
Area Grating
  Type A 28
  Type C (Emer. Exit From Pipe Basement) 28A
  Type B & D 28B

B

Backrest for Self-Care Toilets in
  Spinal Cord Injury Unit 12C
Base, Wainscot and Wall Finish Details 3
Bath Tub Details 14
Bed Wall Outlets - Security
  Room (MS&N Nursing Unit) 26A
Bed Walls Outlets - Single
  Security Bed Room - Psychiatric
  (GEN) Nursing Unit 26D
Bed Wall Outlets Serving Two Beds
  Psychiatric (GEN)
  Nursing Unit 26G
Bed Wall Outlets Serving A Single Bed
  Psychiatric (GEN)
  Nursing Unit 26H
Benches, Types 29, 29A, 29B 52
Bins, Clothing, Types 2 & 3 65
Bins, Type 3A 65A
Bins, X-Ray Film Storage, Type 9 ..... 65B
Book Case, Type 24 54
Bullet Resistive Service Windows for
  Credit Union and Agent Cashier 67
Bullet Resistive Service Window
  and Package Transfer Box
  and Pharmacy 67B
Bulletin Boards & Chalkboards 21
Bumper Guards 57

C

Cabinets
  Cassette Transfer Cabinet 24H
  Types 1A & 1B 70B
  Type 1G 70C
  Type 5A (Wardrobe) 70D
  Type 5B 70E
  Type 6D (Oxidizing Gas Supply) 70F
  Type 8A 70G
  Types 8, 8B & 8C 70H
  Types 11A(Instrument) 70J
  Types 13 & 14 ..... 70K
  Type 14A 70L
  Type 17 (Assembly) 70M
  Type 25 (Display) 70N
  Type 18C (Medicine) 70P
  Kitchen, Types 22 & 22M (Modified) 71
  Kitchen, Types 22C & 22E 71A
  Kitchen, Type 22F 71C
  Kitchen, Type 22G 71D
  Nurse Server, Types S1 and S2 70
Ceiling Bracing for Seismic Forces for Use
  With Acoustical Tile Lay in Ceiling 68
Ceiling Support for X-Ray
  Tube Stand 36
Ceramic Tile Panels (Behind Lavs.) 17
Chalkboards & Bulletin Boards 21
Chancel Plan (Schematic) 25
Chancel Details 25A
Chancel Details 25B
Chapel Casework 25D
Communications Center Counter 27
Construction Sign (A/E Project) 44
Construction Sign (VA Projects) 44B
Corner Guards - Interior 5
Corner Guards - Heavy Duty 6
Counter, Communication Center 27
Counter, Dressing (Make-up), Type B 72A
Counters, Type 1F, 1K, 1L 72C
Counter (Workbench), Type 1M 72D
Counters, Types 15 & 15A 72E
Counters, Types 15B, 15D,
  15E, & 15F 72F
Counters, Types 16, 16A, & 16B 72G
Counters, Types 23 & 28 ..... 72H

Architectural
As of January 1989

C—Continued

Counters, Thru-Wall 72K
Credit Union Office Desk 55
Credit Union Service
Windows & Doors 67

D

Dedication Plaques 50A
Dentistry, Preventive, Patient
Participation Module 53C
Depression (Floor Slab) 1B
Desk in Credit Union Office 55
Details for Tub, Hydrotherapy, Whirlpool,
Space Requirements 4B
Diagramatic Details for Lead Sheilding 24J
Display Cabinet Type 25A 70Q
Divider Strips 39
Door Schedule 7, 7A
Doors to Patients Rooms 7A
Doors Revolving 7C
Door, Lead Lined,
Type 15 and Frames 24E
Door, Lead Lined,
Type 17 and Frame in
C.M.U. Walls 24F
Door, Lead Lined,
Type 17 & Frame in Met.
Stud Partitions 24F1
Dressing Booths (Typical) 12E
Dressing Rooms in Spinal
Cord Injury &
Genito-Urinary Clinics 12F
Drinking Fountain-Wheelchair 4C

E

Electric Water Coolers 4B
Elevators, Passenger
(2-Speed Sliding Doors) 29
Elevators, Passenger-Entrance
Details (2-Speed Sliding Doors) 29A
Elevators, Service
(Center, Opg. Doors) 29B
Elevators, Service & Passenger

E—Continued

Entrance Details (Horizontal Sliding
Center Opg. Doors) 29C
Elevators, Hydraulic 29E
Elevator Hoistways (Passenger)-
Vertical Dimensions 29F
Elevator Hoistways (Service)-
Vertical Dimensions 29G
Elevators Passenger-
Center Opg. Doors 29H
Elevators, Service & Passenger
Entrance Details (with
Drywall Shafts) 29J
Expansion Joint Cover Plates (Interior) 30

F

Fire Apparatus Cabinet, Fire
Extinguisher & Valve Cabinet 56A
Flagpole Details 49
Floor Strips 39
Foundation Drain Detail 40
Frames for Interior Doors 8
Frame for Manually Oper.
Sliding Door 8A
Frames for Automatic Sliding Doors 8B
Front Entrance, Revolving Door 7C

G

Grab Bars & Curtain Rods for Bath Tubs 14
Grab Bars for Sitz Bath 14A
Grab Bar Anchorage 14B
Grab Bar Std.-Water Closet Nurs. Home 14F
Grab Bar-Up Swinging-Water Closet 14G
Nursing Home

H

Hand Rail - Corridor Wall 19
Housekeeping Aid Closet 18

I

Interior Signage 43B
Interior Signage 43C
Interview Booth 41

J

Architectural
As of January 1989

K

L

Ladder Details 33
Lavatories - Typical and Wheel Chair, Spinal 15
Lavatories - Wheel Chair, Spinal
Cord Injury Units 15A
Lead Lining in X-Ray Rooms 24
Lead Lined Block Partitions -
New Construction 24A
Lead Lined Metal Stud Partitions -
New Construction 24B
Lead Lining for Partitions &
Floors in Existing Buildings 24C
Lead Lined Door,
Type 15 and Frame
(Medium X-Ray Protection) 24E
Lead Lined Door,
Type 17 and Frame in
C.M.U. Walls 24F
Lead Lines Door,
Type 17 & Frame in Met.
Stud Partitions 24F1
Lead Framed Control Window 24G
Lead Sleeve for Pipes & Ducts
thru Lead Lines Floor & Walls 24J
Lead Sheet Thickness and Weights 24K
Letter Box and Mail Chute 38
Loading Platform and Canopy 37
Lockers, Metal, Types B& C 61

Lockers, Wardrobe, Types S-3 ..... 61A

M

Metal Stud and Plaster Partitions -
Framing Details 3C
Mirrors Over Lavs 15
Mop Rack, Type 10 ..... 64B
Mirror Filler Plates 15.1

N

Nurses Station .....(See Communication Center Counter)

O

Observation Windows 11

P

Paper Towel Dispenser 53B
Partitions (Metal Stud and Plaster)
Framing Details 3C
Pass Thru, Wall Opening Between
Cashier Office & Travel Office 67A
Pass Window Details 62
Patient Showers 13
Perineal Wall Mounted Sitz
Bath with Grab Bars 14A
Personnel Showers 13A
Plumbing Fixtures 4, 4.1
Plumbing Fixtures -
Furring Requirements 4A
Preventive Dentistry
Patient Participation Module 53C

Q

R

Racks, Mop Type 10 ..... 64B
Rack, Gas Storage 64C
Railing, Corridor Wall 19
Railing at Wall of Therapeutic
Pool Exercise Room 19A
Railing Details 32
Recessed Specimen Pass Box 64
Reinforced Masonry Partitions
for Seismic Forces 68A
Roll-up Door & Grille 7D

S

Seals-Exterior 50
Seats in Dressing Areas 20
Seats in Dressing and Locker
Rooms and Therapeutic Pools 20A
Seismic Forces, Reinforced
Masonry Walls 68A
Self Care Toilet for Spinal
Cord Injury Unit 12B
Service Doors 7D
Service Window for Credit
Union and Agent Cashier 67

Architectural
As of January 1989

S—Continued

Service Window and Package Transfer Box for Pharmacy 67B
Shielding Detail (Neurological Surgical Room) 23
Shielding Detail (Neurological Surgical Room) 23A
Shelf for Wheel Chair Lavs. 15
Shelf - s/s details 15.1
Shelving, Types 4, 4A, & 4B 60
Shelving, Types 5C 60A
Shelving, Types 6, 6A, 6B, 6C, & 6E 60B
Shelving, Types 7, 7A, & 7B 60C
Shelving, Types 7C, 7D, 7E, 7F & 7G 60D
Shelving, Types 35, 37, 37A & 38 ..... 60E
Shelving Library, Types 41M, 41MM, 41P & 41PP 60F
Shelving Library, Types 43M & 43MM 60G
Shelving, Types 44, 45, & 45C 60H
Showers - Patients 13, 13.1, 13.2
Showers - Personnel 13A, 13B
Sign, Building (Exterior) 43A
Sign, Construction 44
Sign, Safety 45
Sink (Vanity, Type S-4) 53
Sink (Vanity, Type S-4M) 53A
Sinks (Vanity, Types S-4 & S-4M) Details 53B
Sink Console Unit for Self-Care Spinal Cord Toilet Room 12D
Sitz Bath Details 14A
Specimen Pass Box 64
Stair Details 10
Stair Tread & Riser Details 10A
Steel Stairs to Service Area 10B
Sub Soil Drain Detail 40
Symbols (Architectural) 1
Symbol of Accessibility for the Handicapped 45A

T

Telephone, Public, Wheel Chair 56
Therapeutic Pool 60' - 0" L x 20' - 0" W—Ward 60' - 0" L x 35' - 0" W 47
Therapeutic Pool 40' - 0" L—30' x 0" W 47A
Toilet Stalls, Urinal Screens 12
Toilet Entry Screening - Wheel Chairs 12A
Toilet Self Care Spinal Cord Injury Unit 12B

T—Continued

Toilet Back Rest for Self-Care Unit in Spinal Cord Injury Unit 12C
Trap Door in Elevator Penthouse Floor 35
Trapeze, Exercise Bar & Patient Helper Suspension Track 14C
Trapeze, Elevations - Typical Locations & Bracing Details 14D
Trapeze Framing, Anchorage & Bracing Details 14E
Tub, Hydrotherapy, Whirlpool Space Requirements 4B

U

Urinal Screens 12

V

VA Logo 44A
Vanity, Wheel Chair Type S-4 53
Vanity, Multiple Wheel Chair—Type S-4M 53A
Vanity, Single, Type S-5 ..... 53D

W

Wall Finish Details 3
Warehouse Receiving Door for Enclosed Dock 37A
Water Cooler - Electric 4C
Wheel Chair Accessibility Symbol 45A
Wheel Chair Accessibility Symbols & Signs for External Use 45B
Wheel Chair Dimensions 42
Wheel Chair Lavatory for Spinal Cord Injury Unit 15A

X

X-Ray Control Window 24G
X-Ray Floor Duct for Cables (Equipment) 22
X-Ray Tube Stand Ceiling Support 36
Plan Of I.V. Track and Ceiling Anchor 36A

Y

Z

Numerical Standard Details Index
Architectural
as of January 1989

Nos.	Title	Date
1	Symbols (Architectural)	June '76
1.1	Symbols (Architectural)	June '86
1.2	Symbols (Architectural)	Jan. '89
1A	Arch. Abbreviations	June '76
1B	Floor Slab Depressions	Dec. '78
3	Base, Wainscot & Wall Details	April '80
3C	Partition Dets. Met. Stud & Plas.	April '80
4	Plumbing Fixtures	Oct. '86
4.1	Plumb. Fixtures	Jan. '89
4A	Plumb. Fixtures Furring Reqmts.	Jan. '81
4B	Details for Tub, Hydrotherapy, Whirlpool; Space Requirements	Sept. '79
4C	Electric Water Coolers	June '86
5	Corner Guards Interior	June '82
6	Corner Guards Heavy Duty	May '80
7	Door Schedule	April '80
7A	Door Schedule	Jan. '89
7C	Front Entrance Revolving Door	April '80
7D	Service Doors	Jan. '79
7E	Ambulance Entrance	June '86
8	Frames for Interior Doors	April '80
8A	Frame for Manually Oper. Sliding Doors	March '78
8B	Frames for Auto. Sliding Doors	April '80
10	Stair Details (Exit Stairs)	Oct. '86
10A	Stair Tread & Riser Details	April '80
10B	Stairs, Fixed Industrial	April '80
11	Observation Windows	Feb. '86
12	Toilet Stall, Urinal Screens & Dressing Booths	June '86
12A	Toilet Entry Screening Wheelchair	Oct. '83
12B	Self-Care Toilet for Spinal Cord Injury Use	March '82
12C	Backrest for Self-Care Toilets in S.C.I. Units	April '80
12E	Typical Dressing Booths	June '78
12F	Dressing Rooms in Spinal Cord Injury & Genito-Urinary Clinics	June '86
13	Patient Showers	June '86
13.1	Shower - Patient Wheelchair Accessible	Jan. '89
13.2	Shower - Patient Wheelchair Accessible	Jan. '89
13A	Personnel Shower (Single Use Area)	Jan. '89
13B	Personnel Shower (Multiple Use Area)	Jan. '89
14	Grab Bars & Curtain Rods for Bath Tubs	June '86
14A	Sitz Bath Details	June '86
14B	Grab Bar Anchorage	April '80
14C	Trapeze Exercise Bar & Patient Helper Suspension Tracks	April '86
14D	Trapeze Elev. Typ. Locations & Bracing Details	April '80
14E	Trapeze Framing Anchorage and Dimensions	April '80
14F	Standard Grab Bar For Water Closet in Nursing Home	Jan. '89
14G	Up-Swinging Grab Bar For Water Closet, Nursing Home	Jan. '89
15	Lavatory Typ. Wheelchair	Oct. '86
15.1	Mirror Filler Plate & S/S Shelf Details	Jan. '89
15A	W/C Lavatory for Spinal Cord Injury Units	June '82
15B	Lavatory Support	June '86
17	Ceramic Tile Panels	April '80
18	Housekeeping Aid Closet	Jan. '81
19	Railing, Corridor Wall	Sept. '76
19A	Railing at Walls of Thera. Pool Exercise Rm.	Jan. '76
20	Seats in Dressing Areas	Apr. '80
20A	Seats in Dressing & Locker Rooms and Thera. Pool	April '80
21	Chalkboards and Bulletin Boards	April '80
22	X—Ray Floor Duct for Cables to Equipment	June '82

Numerical Standard Details Index-
Architectural
as of January 1989

Nos.	Title	Date
24	Lead Lining in X-Ray Rooms	April '80
24A	Lead Lined Block Partitions-New Construction	April '80
24B	Lead Lined Metal Stud Partns.- New Construction	April '80
24C	Lead Lining for Partns.; & Floors in Existg. Bldgs.	April '80
24E	Lead Lined Door Type 15 & Frame	April '80
24F	Lead Lined Door Type 17 & Frame (In CMU Walls)	April '80
24F1	Lead Lined Door Type 17 & Frame (In Metal Stud Partns.)	April '80
24G	Lead Framed Control Window	April '80
24H	Cassette Transfer Cabinet	July '69
24J	Lead Sleeve for Vert. Pipes Passing Thru Lead Lined Floor	July '69
24K	Lead Sheet Thickness & Weights	July '69
25	Chancel Details (Schematic)	April '80
25A	Chancel Details (Altar & Com. Rail)	April '80
25B	Chancel Details (Ark & Predella)	April '80
25D	Chapel Casework (R&S Details)	July '69
26A	Bed Wall Outlets Security Room (MS&N Nurse Unit)	July '69
26D	Bed Wall Outlets - Single Security B.R. Pscy. (General) Nursing Unit	March '78
26G	Bed Wall Outlets - Service a Single Bed Psychiatric (Gen.) Nurse Unit	March '78
26H	Bed Wall Outlets Service @ Beds Psychiatric (Gen.) Nurse Unit	July '82
27	Communication Center Counter	July '69
28	Area Grating Type "A"	April '80
28A	Area Grating Type "C" (Emerg. Exit from Pipe Bsmt.)	April '80
28B	Types B&D	April '80
29	Elevators, Passenger (2-Speed Slid. Doors)	April '80
29A	Elevators-Passenger Ent. Dets. 2-Speed Sliding Doors	April '80
29B	Elevators, Service (Horiz. Sliding Center Opg. Doors)	April '80
29C	Elevators-Serv. & Pass. Entrance Details Center Opg. Doors	Dec. '80
29D	Freight Elevator	April '80
29E	Elevators, Hydraulic	April '80
29F	Elevators Hoistways (Passenger) Vert. Dims	April '80
29G	Elevators Hoistways (Service) Vert. Dims	April '80
29H	Elevators, Passenger Horiz. Slid. Center Opg.	April '80
29J	Elevators, Service & Passenger Ent. Dets. W/Drywall Shaft	April '80
30	Expansion Joint Cover Plates	April '80
32	Railing Details	Sept. '79
33	Ladder Details	Jan. '79
34	Access Door (Wire Mesh) and Ladder	May '80
35	Trap Door in Elevator Penthouse	June '82
36	Ceiling Support for X-Ray Tube Stand	March '80
36A	Plan I.V. Track and Ceiling Anchor	June '82
37	Loading Platform and Canopy	June '82
37A	Warehouse Receiving Door for Enclosed Dock	March '78
38	Letter Box and Mail Chute	July '77
39	Floor Strips	June '78
40	Sub Soil Drain Detail	Jan. '79
41	Interview Booth	Dec. '80
42	Wheelchair Dimensions	Dec. '80
43A	Bldg. Sign	April '86
43B	Interior Signage	Jan. '81
43C	Interior Signage	Oct. '83
44	Construction Sign (For A/E Working Dwgs.)	March '82
44A	VA Logo	Oct. '83
44B	Construction Sign (For VA Working Dwgs.)	Jan. '76
45	Safety Sign	Jan. '76
45A	Symbol of Accessibility to the Handicapped	

Numerical Standard Details Index-
Architectural
as of January 1989

Nos.	Title	Date
47	Therapeutic Pool 60' x 28'	Oct. '83
47A	Therapeutic Pool 40' x 33'	Sept. '79
49	Flagpole Details	April '80
50	Seals Exterior	Dec. '82
50A	Dedication Plaques	Sept. '79
52	Benches Types 29, 29A, 29B	June '82
53	Vanity Type S4	June '86
53A	Vanity Type S4M	April '86
53B	Paper Towel Dispenser	June '86
53C	Preventive Dentistry* Patient Participation Module	Jan. '79
53D	Vanity, Single, Type S5	June '86
54	Bookcase Type 24	Dec. '74
55	Desk in Credit Union Office	Dec. '74
56	Standard & W/C Tele. Cabinets	April '80
56A	Fire Apparatus Cabinet, Fire Extinguisher & Valve Cabinet	April '80
57	Interior Wall Bumper Guards	July '77
58	Ambulance Entrance Details for Head-In or Drive-Thru Unloading	Sept. '79
59	Ambulance Entrance Details for Back-In Unloading	Sept. '79
60	Shelving - Types 4, 4A & 4B	June '76
60A	Shelving Type 5C	Dec. '74
60B	Shelving Types 6, 6A, 6B, 6C & 6E	June '76
60C	Shelving Types 7, 7A, & 7B	April '80
60D	Shelving Types 7C, 7D, 7E, 7F & 7G	Dec. '74
60E	Shelving Types 35, 37, 37A & 38	April '80
60F	Library Shelving 41M, 41MM, 41P & 41PP	Dec. '74
60G	Library Shelving Types 43M & 43MM	Dec. '74
60H	Shelving Types 44, 45 & 45C	Dec. '74
61	Lockers Metal Types A, B, C, &D	July '77
61A	Lockers, Wardrobe, Type S3	July '77
62	Pass Window Details	Jan. '79
64	Recessed Specimen Pass Box	Jan. '81
64B	Mop Rack Type 10	June '82
64C	Gas Storage Rack	Sept. '79
65	Bins, Clothing Types 2 & 3	Dec. '74
65A	Bins Type 3A	Dec. '74
65B	Bins, X-Ray Film Stor. Type 9	Dec. '74
66	Anchorage for Wall Mounted Items	July '77
67	Service Window for Credit Union & Agent Cashier	Sept. '79
67A	Pass Thru, Wall Opg. Between Cashier Off. & Travel Office	Sept. '79
67B	Service Window & Package Transfer Box for Pharmacy	Sept. '80
68	Ceiling Bracing for Seismic Forces	Jan. '79
68A	Reinforced Partns. Masonry-(For Seismic)	June '75
70	Cabinets, Nurse Server S1 & S2	April '78
70A	Nurse Server S1 & S2, Details	Oct. '70
70B	Cabinets Types 1A, 1B & 1C	June '78
70C	Assembly Type 1G	June '82
70D	Cabinet Type 5A	June '76
70E	Cabinet Type 5B	Dec. '74
70F	Cabinet Type 6D	Dec. '74
70G	Tool Cabinet Type 8A	Jan. '76
70H	Cabinets Types 8, 8B & 8C	July '77

Numeric Standard Detail Index-
Architectural
as of January 1989

Nos.	Title	Date
70j	Cabinet Type 11A (Instrument)	Dec. '74
70K	Cabinets Types 13 & 14	Dec. '74
70L	Cabinet Type 14A	Dec. '74
70M	Cabinet Type 17	July '77
70N	Cabinet, Display, Type 25	Dec. '74
70P	Medicine Cabinets Type 18C	March '78
70Q	Display Cabinet Type 25A	June '78
71	Kitchen Cabinet Type 22 & 22 Modified	June '76
71A	Kitchen Cabinets Types 22C & 22E	July '77
71C	Kitchen Cabinets Type 22F	July '77
71D	Kitchen Cabinet Assy. Type 22G	July '77
72A	Counter Dressing (Make-Up) Type B	Jan. '81
72C	Counter Types, 1F, 1K & 1L	Jan. '81
72D	Counter Workbench Type 1M	July '77
72E	Counter Types 15 & 15A	Jan. '81
72F	Counter Types 15B, 15D, 15E & 15F	Jan. '81
72G	Counter Types 16, 16A & 16B	June '82
72H	Counter Types 23 & 28	Jan. '81
71K	Thru-Wall Counters	Jan. '81

029181

PLAN + SECTION INDICATIONS

EARTH


GRAVEL FILL


CONCRETE


CMU

BRICK


PLASTER, SAND/GROUT

MARBLE

IRON/STEEL


METAL STUD


GWB

FINISHED WOOD

ROUGH WOOD


PLYWOOD


BATT INSULATION


RIGID INSULATION


CERAMIC TILE


ACOUSTIC TILE

ELEVATION INDICATIONS


GLASS

PLASTER


CONCRETE


BRICK


CERAMIC TILE

METAL

1

Title
ARCHITECTURAL MATERIAL SYMBOLS

Date Issued
1/30/89

Revision

Notes

PLAN + SECTION INDICATIONS

EARTH


GRAVEL FILL


CONCRETE

CMU

BRICK

PLASTER, SAND/GROUT

MARBLE

IRON/STEEL


METAL STUD


GWB

FINISHED WOOD

ROUGH WOOD

PLYWOOD

BATT INSULATION


RIGID INSULATION


CERAMIC TILE

ACOUSTIC TILE

ELEVATION INDICATIONS

GLASS


PLASTER


CONCRETE


BRICK


CERAMIC TILE

METAL

1	Title: ARCHITECTURAL MATERIAL SYMBOLS	Date Issued: 1/30/89 Revision:	Notes



STRUCTURAL GRID
COLUMN TAG



ROOM NAME
ROOM NUMBER



DETAIL NUMBER
DRAWING NUMBER



SECTION NUMBER
DRAWING NUMBER

WINDOW NUMBER
SEE WINDOW SCHEDULE

LOUVER NUMBER
SEE LOUVER SCHEDULE



NEW PARTITION
SEE PARTITION SCHEDULE

PARTITION NUMBER



EXISTING CONSTRUCTION
TO BE REMOVED

EXISTING DOOR AND
FRAME TO REMAIN



EXISTING DOOR AND
FRAME TO BE REMOVED



HARDWARE NUMBER
SEE SPECIFICATIONS

NEW DOOR AND FRAME

DOOR SYMBOL
SEE DOOR SCHEDULE

LEAD LINED
PARTITION

SOUND INSULATED
PARTITION



SMOKE
PARTITION



1 HOUR FIRE
RATED PARTITION



2 HOUR FIRE
RATED PARTITION



1 HOUR FIRE + SMOKE
RATED PARTITION



2 HOUR FIRE + SMOKE
RATED PARTITION

1.1

Title
ARCHITECTURAL
SYMBOLS

Date Issued
1/30/89

Revision

Notes



STRUCTURAL GRID
COLUMN TAG

ROOM NAME
ROOM NUMBER

DETAIL NUMBER
DRAWING NUMBER



SECTION NUMBER
DRAWING NUMBER

WINDOW NUMBER
SEE WINDOW SCHEDULE

LOUVER NUMBER
SEE LOUVER SCHEDULE



NEW PARTITION
SEE PARTITION SCHEDULE

PARTITION NUMBER

EXISTING CONSTRUCTION
TO BE REMOVED



EXISTING DOOR AND
FRAME TO REMAIN



EXISTING DOOR AND
FRAME TO BE REMOVED



HARDWARE NUMBER
SEE SPECIFICATIONS

NEW DOOR AND FRAME



DOOR SYMBOL
SEE DOOR SCHEDULE

LEAD LINED
PARTITION

SOUND INSULATED
PARTITION

SMOKE
PARTITION

1 HOUR FIRE
RATED PARTITION

2 HOUR FIRE
RATED PARTITION

1 HOUR FIRE + SMOKE
RATED PARTITION

2 HOUR FIRE + SMOKE
RATED PARTITION

1.1

Title
ARCHITECTURAL
SYMBOLS

Date Issued
1/30/89

Revision

Notes

EQUIPMENT SYMBOL
SEE EQUIPMENT SCHEDULE

—x—x— CUBICLE CURTAIN TRACK

FLUORESCENT FIXTURE

VV ITEM
V.A. SUPPLIED
V.A. INSTALLED

WALL MOUNTED
OXYGEN, AIR AND
VACUUM OUTLETS

O A V

INCANDESCENT FIXTURE

VC ITEM
VA SUPPLIED
CONTRACTOR INSTALLED

SUPPLY DIFFUSERS

CC ITEM
CONTRACTOR SUPPLIED
CONTRACTOR INSTALLED

RETURN GRILLE

FCU

FAN COIL UNIT

Veterans Administration

1.2

Title
ARCHITECTURAL
SYMBOLS

Date Issued
1/30/89

Revision

Notes

ABBREVIATIONS (ARCHITECTURAL)

A.B	Anchor Bolt
A/C	Air Conditioned
A.C.U.	Air Conditioning Unit
A.D.	Access Door
Adj.	Adjustable
A.D.O	Automatic Door Operator
ALUM.	Aluminum
A.P.	Access Panel
AT	Acoustical Tile
B.BD.	Bulletin Board
B.P.R.	Bed Pan & Urinal Rack
C, CONC.	Concrete
CAB.	Cabinet
C.B.	Chalk Board
C.C.T.	Cubicle Curtain Track
C.C.U.	Coronary Care Unit
CEM.	Cement
C.F.I.	Conductive Flooring
C.I.	Cast Iron
C. G.	Corner Guard
C.J.	Control Joint
CLG.	Ceiling
CL.GL.	Clear Glass
CLO.	Closet
C.M.U.	Concrete Masonry Unit
CNL	Conductive Neoprene Latex
COL.	Column
CONT.	Continuous
CONST.	Construction
CP.	Carpet
C.S.	Cup Sink
C.T.	Ceramic Tile
C.T.P.	Ceramic Tile Panel
CTR.	Counter
C.V.H.	Conductive Vinyl Homogenous (Sheet Type)
D.F.	Drinking Fountain
DIA.	Diameter
DIAG.	Diagonal
D.L.	Dental Laboratory
Dim.	Dimension
DISP.	Dispenser
D.S.	Downspout
D.S.B.	Double Strength "B" Quality Glass
D.W.	Dumbwaiter
DWGS.	Drawings
E.E.G.	Electro Encephalographic
ELEC.	Electrical
ELEV, EL.	Elevation
ELEV.	Elevator
E.J.	Expansion Joint
E.K.G.	Electro Cardiograph
E.N.T.	Ear, Nose & Throat
E.P.	Electric Panel
EPY.	Epoxy Coating
EQUIP.	Equipment
(E), EX., EXIST.	Existing
EXT.	Exterior
E.W.C.	Electric Water Cooler
EXP.	Exposed, Expansion
F.A.C.	Fire Apparatus Closet
F.A.I.	Fresh Air Intake
F.C.U.	Fan Coil Unit
F.D.	Floor Drain
F.H.R.	Fire Hose Rack
F.I.	Film Illuminator
FIN.	Finish
FL	Floor
F.P.	Fire Partition
F.S.	Full Size
FTG.	Footing
GA.	Gauge
G.B.	Grab Bar
GL.	Glass
GR.	Grade
G W	Gypsum Wall Board
GYP.	Gypsum
H.A.C.	Housekeeping Aides Closet
HTG.	Heating
H.M.	Hollow Metal
H.P.	High Point
HW.	Hardware
H.B.	Hose Bibb.
I.C.U.	Intensive Care Unit
I.D.	Inside Diameter
INSUL.	Insulation
INT.	Interior
I.P.S.	Inside Pipe Size
I.V.	Intra-Venous
JT.	Joint
KIT.	Kitchen
K.P.	Kick Plate
L, LAV.	Lavatory
L.C.	Laundry Chute
LKR.	Locker
L.L.D.	Lead Lined Door
L.P.	Low Point
L.P.D.	Light Proof Door
L.P.S.	Light Proof Shade
M	Modular Laboratory Equipment (Interchangeable)
MAX.	Maximum
M.C.O.	Metal Cased Opening
M.D.S	Metal Divider Strip
MECH.	Mechanical
MED.CAB.	Medical Cabinet
M.E.S.	Metal Edge Strip
MET.	Metal
MIN.	Minimum
MISC.	Miscellaneous
MLDG.	Moulding
M.N.I.C	Material Not in Contract (Installation By Contractor)
M.O.	Masonry Opening
MOD.	Modified
M.P.	Movable Partition
M.T.	Metal Threshold
MTD.	Mounted
(N)	New
N.I.C.	Not In Contract
N.L.	Neoprene Latex
NOM.	Nominal
N.P.	Neuropsychiatri
OBS	Obscure
O.C.	On Center
O.D.	Outside Diameter
OPNG	Opening
OPP.	Opposite
O.T.	Occupational Therapy
O.W.	Observation Window
P	Paint
PART'N(S)	Partition(s)
P.B.P.U.	Patients Bedside Power Unit
P.I.P.U.	Prefab. Isolation Power Unit
PL	Plate
PLAS., PL.	Plaster
PLWD	Plywood
PORT.	Portable
P.P.G.	Polished Plate Glass
P.R.V.	Power Roof Ventilator
P.S.	Pipe Space
P.T.	Pneumatic Tube
P.W.	Pass Window
Q.T.	Quarry Tile
(R)	Relocated Item
R	Riser
R.D.	Roof Drain
RECEP.	Receptacle
REF.	Refrigerator
REG.	Reglet
REINF.	Reinforcing, Reinforced
REQ'D.	Required
RM.	Room
R.O.	Rough Opening
R.P.	Retractable Partition
S.C.	Special Coating
SCHD.	Schedule
S.C.I.	Spinal Cord Injury
SEC.	Section
S.F.T.U	Structural Facing Tile Unit
SH.	Shelving, Shelf
SIM.	Similar
S.P.D.	Sound Proof Door
SPEC.(S)	Specification(s)
S & R	Shelf & Rod
STRUCT.	Structural
S/S, S.S	Stainless Steel
TEL.	Telephone
TERR.	Terrazzo
T.T.	Terrazzo Tile Resinous Matrix
TOIL, T.	Toilet
V	Vinyl
V.A.	Vinyl Asbestos
VEST.	Vestibule
V.H.	Vinyl Homogenous
W.	Wall Fabric
W.C.	Water Closet
W/C	Wheel Chair
WD.	Wood
W.C.O.	Wood Cased Opening
W.D.	Window Dimension
W.I	Wrought Iron
W.P.	Waterproof(ing)
W.R.	Waste Receptacle

ABBREVIATIATIONS FOR DETAILS OF WOOD AND METAL WORK

E.B.	Expansion Bolts	O.H.	Oval Head
M.B.	Machine Bolts	P.H.	Pan Head
M.S.	Machine Screws	R.H.	Round Head
S.M.S.	Sheet Metal Screws	SQ.HD.	Square Head
W.S.	Wood Screws	T.H.	Truss Head
CSK.	Countersunk	PL.	Plate
F.H.	Flat Head or Flush Head	S.M.	Sheet Metal
		GA.	Gauge

ABBREVIATIONS FOR MISCELLANEOUS CASE-WORK, SHELVING, EQUIPMENT, ETC. IDENTIFIED BY TYPE NUMBER AND/OR LETTER ON ARCHITECTURAL PLANS

EXAMPLE

C-8	Cabinet Type 8
B	Bins
B.C.	Bookcase
BE.	Bench
C	Cabinet
CTR.	Counter
K	Kitchen Equipment
P	Plumbing Fixture
RK.	Rack
R&S	Casework in Clergy Room & Sacristy, Chaplain Service
TA	Table
V L	Clinical Laboratory Equipment
V. R.	Radio Isotope Lab. Equipment
V. S.	Sterilizer
D. C.	Dental Casework
M	Laboratory Equipment Modular Interchangeable
S	Casework in Patients Bedroom And Service Alcove
X	X-Ray Equipment Radiology
MOD.	Modified

NOTE: THIS SCHEDULE SHALL BE UTILIZED BUT EDITED AND ADDED TO AS NECESSARY FOR EACH SPECIFIC PROJECT.

IA

NOTE:
See Sheet No. 7 For Abbreviations Used With Door Symbols.

AREA OR ROOM:	SLAB DEPRESSION
CERAMIC TILE FLOOR WITHOUT DRAIN	0"
CERAMIC TILE FLOOR WITH SLOPE TO DRAIN	4"
QUARRY TILE FLOOR WITHOUT DRAIN	2"
QUARRY TILE FLOOR WITH SLOPE TO DRAIN	4"
TERRAZZO FLOOR	2"
COLD ROOM, RESEARCH	0" (SEE NOTE No. 3)
CONSTANT TEMPERATURE ROOMS	0" (RAISED FLOOR)
ALL FREEZERS AND REFRIGERATORS	4" PLUS FINISH (SEE NOTE No. 5)
R.F.I. SHIELDED ROOM	1 1/2"
LEAD SHIELDED ROOMS	5"
ANIMAL CAGE WASHER	12 1/2" TO 13 1/2" (SEE NOTE No. 4)
CART WASHER WITH TRANSPORT SYSTEM	12" TO 16" (SEE NOTE No. 4)
CART WASHER WITHOUT TRANSPORT SYSTEM	12" TO 18" (SEE NOTE No. 4)
AUDIO TESTING & CONTROL (PREFABRICATED UNITS)	
SINGLE FLOOR UNIT	7"± (SEE NOTE No. 6)

NOTE: R.F.I. = RADIO FREQUENCY INTERFERENCE

NOTES TO ARCHITECT:

1. DEPRESSIONS SHOWN ABOVE ARE TO BE BELOW TOP OF NORMAL FINISHED FLOOR.
2. OMIT DEPRESSIONS WHERE THICKNESS OF TOPPING OR FILL IS AS MUCH AS OR GREATER THAN DEPRESSION SHOWN ABOVE.
3. RESEARCH COLD ROOMS MAY HAVE DEPRESSION AS REQUIRED TO ACCOMMODATE THE EQUIPMENT AND FINISH SPECIFIED 4". IF NO DEPRESSION IS PROVIDED, THE ROOM WILL HAVE A RAISED FLOOR.
4. DEPRESSIONS FOR ANIMAL CAGE WASHERS AND CART WASHERS SHALL BE DESIGNED TO ACCOMMODATE THE EQUIPMENT SPECIFIED.
5. DEPRESSIONS FOR FREEZERS AND REFRIGERATORS SHALL BE DESIGNED TO ACCOMMODATE THE EQUIPMENT SPECIFIED PLUS THE ADDITIONAL DEPTH NECESSARY FOR THE REQUIRED FLOOR FINISH.
6. DEPRESSIONS FOR PREFAB AUDIO TESTING AND CONTROL ROOM UNITS SHALL BE AS REQUIRED FOR THE EQUIPMENT AND FLOOR FINISH SPECIFIED.
7. THE ABOVE FLOOR SLAB DEPRESSIONS DO NOT NECESSARILY CONSTITUTE ALL THE SLAB DEPRESSIONS THAT MAY BE REQUIRED FOR A PARTICULAR PROJECT, NOR SHALL THEY BE EXACTLY MAINTAINED IF THE EQUIPMENT TO BE USED, OR ANY OTHER CONDITIONS INDICATE THAT THEY SHOULD BE MODIFIED.

Jan. '81

IB

FLOOR SLAB DEPRESSIONS

DEC. '78







4	Title BASE, WAINSCOT & WALL FINISH DETAILS	Date Issued 1/30/89 Revision

Notes

Title PLUMBING FIXTURES

Date issued 1/30/04

Revision

Notes

Architectural Standard 4

P-101 P-103, P-107, P-110, P-111

P-102 (WALL HUNG) P-104 (WALL MTD)

P-106 P-105 (WALL MTD)

FLUSH VALVE WALL MOUNTED TANK TYPE

WATER CLOSETS (P-100 SERIES)

P-201 P-203

P-202 (FOOT PEDAL)

(WALL MTD)

(P-200 SERIES)

P-401 P-408 (18x15)

P-402

P-403

P-405 (20x18)

P-406

P-407 ← W/C GOOSE NECK

P-414 ← W/C

P-415

P-418

P-409 (CORNER TYPE) (17"x17")

P-412

(WALL HUNG)

(SEMI-RECESSED)

P-411 (SURGEONS LAV. W/ INST. TRAY) (28x20")

P-404 (21x13")

P-410 W/C (SPINAL USE) (27"x20")

P-413

P-417

19" DIAM

LAV. FIXTURES (P-400 SERIES)

P-304 PIER TYPE

WALL LINE

P-305 (SITZ)

P-302

P-307

(RECESSED TYPE)

(RIGHT ANGLE)



P-501 (FL. MTD)
P-503 (FOOT PEDAL)

P-502
(FL. SET)

SERVICE SINK



P-505
(WALL MTD W/ TWO FOOT PEDALS)
FLUSHING RIM

SERVICE SINK



P-506
(WALL MTD)

ENEMA SINK (MOP TYPE)



P-507
(WALL MTD W/ PLASTER TRAP ON FLOOR)

PLASTER SINK



30 x 20 P-508 (WALL MTD)
29 x 20 P-511 (WALL MTD & FOOT PEDAL)
30 x 18 P-515
30 x 20 P-516
20 x 14 P-517
(WALL MTD)

S/S SINK

P-509
WALL MTD W/ FOOT CONTROL & DRAIN BD

ALL PURPOSE SINK



42x20 P-510
54-20 P-512
48-24 P-514
(WALL MTD W/ FOOT PEDAL & DRAIN BD EITHER SIDE)

S/S SINK



84"x24" P-513 (DOUBLE DRAIN BD W/ FOOT PEDAL)

S/S SINK



P-518 FLOOR MTD
9'-0" x 2'-3"



P-521
P-527 W/LEGS & PLASTER TRAP

LAV. TUB (PLASTIC)

P-525 WALL-HUNG FPC

SURGEON SCRUB-UP SINK

DOUBLE COMP. S/S SINK

P-522 50x22
P-524 33x22
DOUBLE COMPARTMENT

Notes

Date Issued 1/30/19

Revision

Title PLUMBING FIXTURES

Veterans Administration Standard Detail

A1



WATER CLOSETS IN BATTERY



WATER CLOSETS BACK TO BACK



WATER CLOSET - SINGLE



URINAL - SINGLE

A4

Title
PLUMBING FIXTURES
FURRING REQUIREMENTS

Date Issued
1/31/11

Revision

Notes
SCALE 1"-1'-0"



PLAN

HT101



PLAN

HT102
HT103



PLAN

HT104



PLAN

HT113



ELEVATION

FULL BODY

HT101



ELEVATION

LEG

HT102
HT103



ELEVATION

ARM

HT104



ELEVATION

BATH

HT113

NOTES

1. CLEARANCE AROUND SIDE AND FRONT OF EACH UNIT, SHOULD HAVE A MINIMUM OF 3'-0" FROM ANY OBSTRUCTION, SUCH AS-CURTAINS, WALLS & 6'-0" TO ANOTHER UNIT, WITH THE EXCEPTION OF ITEM HT101.
2. THE UNITS SHALL NOT BE PLACED CLOSER THAN 9" MINIMUM FROM THE WALL
3. UNIT, HT101 TO HAVE A OVER-HEAD MONO-RAIL WITH AN ELECTRIC HOIST.

DETAILS FOR TUB, HYDROTHERAPY, WHIRLPOOL; SPACE REQUIREMENTS

TITLE

DATE ISSUED Sept. '79 | REVISION

4B

Veterans Administration STANDARD DETAIL



MOULDING DETAIL
SCALE: 1/2 SIZE



ELEVATION
SCALE: 3/4" = 1'-0"



PLAN. ELECTRIC WATER COOLER FOR SCI UNIT.
SCALE: 3/4" = 1'-0"



HALF PLAN W/O ALCOVE
SCALE: 3/4" = 1'-0"

HALF PLAN ALCOVE CONDITION
ELECTRIC WATER COOLER
FOR HOSPITAL AREA EXCEPT SCI UNIT

4C

Title
ELECTRIC WATER COOLERS

Date issued
11/30/89

Revision

Notes

OCB T D
9/29/87



MOULDING DETAIL
SCALE: 1/2 SIZE



ELEVATION
SCALE: 3/4" = 1'-0"



PLAN ELECTRIC WATER COOLER FOR SCI UNIT
SCALE: 3/4" = 1'-0



HALF PLAN W/O ALCOVE
SCALE: 3/4"=1'-0"

HALF PLAN ALCOVE CONDITION
ELECTRIC WATER COOLER
FOR HOSPITAL AREA EXCEPT SCI UNIT

A C	**Title** ELECTRIC WATER COOLERS	**Date Issued** 11/30/89 **Revision**	**Notes** OLBTD 9/29/87



PLAN

PLAN



SECTION AT BASE

SURFACE MOUNTED RESILIENT CORNER GUARDS

SECTION AT BASE

RECESSED RESILIENT CORNER GUARDS

5

Title
INTERIOR RESILIENT CORNER GUARDS

Date Issued
1/30/87

Revision

Notes 1. CG'S SHALL TERMINATE AT TOP OF WAINSCOTE OR 4" ABOVE FL WHERE THERE IS NO WAINSCOTE.



3-1¼" x 3/16" STRAP ANCHORS 9" LONG @ 16" O.C. FIRST ANCHOR @ 8" A.F.F. WHERE BRICK FACING OCCURS AT CONC. COLUMN, BEND STRAP ANCHORS & SECURE TO COLUMN WITH EXP. BOLT.

4"x4"x¼"x4'-0" HIGH STEEL ANGLE (CAULK TOP & ALL EDGES)

BRICK OR C.M.U. (FILL NEAREST C.M.U. CELL SOLID WITH CONC. OR USE SOLID C.M.U.)

EXPOSED BRICK OR C.M.U.



3 - 5/8" ϕ x 6" LONG CONC. ANCHORS WELDED TO ANGLE @ 16" O.C. FIRST ANCHOR @ 8" A.F.F.

4"x4"x¼"x4'-0" HIGH STEEL ANGLE

CONC. WALL OR COLUMN.

EXPOSED CONC. WALL OR COLUMN.

TYPICAL CORNER GUARDS (HEAVY DUTY)

SCALE: 3" = 1'-0"

Notes: 1. WHERE ANGLE GUARD (4"x4"x¼") IS INSTALLED ON EXISTING MASONARY, USE EXP. BOLTS IN LIEU OF STRAP ANCHORS.
2. EXPOSED TOP EDGES OF ANGLES SHALL BE GROUND SMOOTH & SLIGHTLY ROUNDED & CAULKED.

Date Issued	Revision
1/30/79	

Title: CORNER GUARDS - HEAVY DUTY.

Veterans Administration Standard Detail

6.



Title
DOOR SCHEDULE

Date Issued
1/31/19

Revision

Notes

7

DOOR SIZES

MARK	WIDTH	HEIGHT	MARK	WIDTH	HEIGHT
A	1'-6"	6'-8"	N	2'-0"	7'-0"
B	2'-0"	6'-8"	O	2'-2"	7'-0"
C	2'-2"	6'-8"	P	2'-4"	7'-0"
D	2'-4"	6'-8"	Q	2'-6"	7'-0"
E	2'-6"	6'-8"	R	2'-8"	7'-0"
F	2'-8"	6'-8"	S	3'-0"	7'-0"
G	2'-10"	6'-8"	T	3'-4"	7'-0"
H	3'-0"	6'-8"	U	3'-6"	7'-0"
I	3'-2"	6'-8"	V	3'-8"	7'-0"
J	3'-4"	6'-8"	W	3'-10"	7'-0"
K	3'-8"	6'-8"	X	4'-0"	7'-0"
L	3'-10"	6'-8"	Y	3'-0"	8'-0"
M	1'-6"	7'-0"	Z	UNASSIGNED	

DOOR MODIFICATIONS

A LAMINATED GL.

D DOUBLE GLAZED TEMPERED GL.

H ELECTRIC HOLD

L LOUVER

LP LIGHT PROOF LOUVER

M MECH. SEAL FOR LIGHT PROOF & SOUND RETARDING DR

T TEMPERED GL

U UNDERCUT 1"

X LEAD GL

W WIRE GL

DOOR SYMBOL



LEGEND (SEE DR. ELEVATIONS)

GL. OR L. REQUIRED BY MODIFICATION

GL. OR. L REQUIRED BY ELEVATION TYPE

NOTES:

1 ALL DOORS SHALL BE FLUSH & 1¾" THICK UNLESS NOTED OTHERWISE

2 TOP & SIDE RAILS SHALL BE 9" MIN., BOTTOM RAILS 12" MIN.

3. DOOR TYPES 7, 8 & 9 SHALL NOT BE USED FOR OPPOSING DOORS

4 FOR SCHEDULING DOOR TYPES SEE H-08-14

5 ON THE DR TYPE SCHEDULE EVEN DR. NOS ARE FOR MET. DRS, ODD NO.S ARE FOR WOOD DRS.

Notes

Date Issued 1/30/89

Revision

Title DOOR SCHEDULE

7.A



PLAN



ELEVATION



SECTION (1)



SECTION (2)



SECTION (3)



SECTION (4)

NOTES

FRONT ENTRANCE - REVOLVING DOOR

TITLE

DATE ISSUED APRIL '60 REVISION

7C

Veterans Administration STANDARD DETAIL



NOTES TO ARCHITECT:

1. ROLL-UP GRILLE SHALL BE CHAIN OPERATED & PROVIDED WITH A LOCK.
2. ROLL-UP DOORS SHALL BE MOTOR OPERATED OR MANUALLY OPERATED AS DETERMINED ON AN INDIVIDUAL BASIS. IF MOTOR OPERATED, AUXILIARY MANUAL OPERATION SHALL ALSO BE PROVIDED.
3. THE ARCHITECT SHALL PROVIDE FOR ROLL-UP GRILLES AT ALL ROLL-UP DOORS UNLESS SPECIFICALLY INSTRUCTED OTHERWISE BY THE VETERANS ADMINISTRATION.

ROLL- UP DOOR AND GRILLE DETAILS- SCHEMATIC

(FOR USE AT WAREHOUSES, BOILERPLANTS OR SIMILAR PLACES)

OVERHEAD DOORS FOR AMBULANCE ENTRANCE GARAGES-SCHEMATIC
(ELECTRICALLY OPERATED)



ELEVATION



SECTION

SERVICE DOORS

TITLE

DATE ISSUED JAN.'79

REVISION

NOTES

1. PROVIDE NEOPRENE RUBBER SEAL AT JAMBS, HEAD & BOTTOM OF DOOR.
2. NO THRU-WALL SUPPORT FASTENINGS PERMITTED FOR HOUSING.
3. DOOR TRACKS AND ALL OTHER HARDWARE AND MECHANISMS SHALL BE AS REQUIRED BY MFGR. FOR SPECIFIC DOOR(S) USED.

Veterans Administration STANDARD DETAIL

7D

GENERAL NOTES:

1. EXTERIOR DOOR OPERATION DETERMINED BY STATION
2. SPACE NOT HEATED AND PROVIDE MINIMAL LIGHTING WHEN UNOCCUPIED.
3. PROVIDE WINTER/SUMMER SWITCH TO DISCONNECT HEATER IN SUMMER. ALSO PROVIDE THERMOSTAT.
4. EXHAUST FANS TO BE TIME DELAY SHUTOFF FOR PROPER EXHAUST CLEARING.

NOTES

1. MAXIMUM DIMENSIONS ARE REQUIRED BY FEDERAL STANDARDS. MINIMUM DIMENSIONS MAY BE USED WHERE SPACE IS LIMITED.

7E	Veterans Administration STANDARD DETAIL	TITLE
		DATE ISSUED 6/18/86
		REVISION



MASONRY BLOCK WITH CERAMIC TILE FINISH



TILE FINISH



FRAMES IN METAL STUD PARTITIONS



NOTE:

SHOWING THE SWING OF DOUBLE EGRESS DOORS



MASONRY BLOCK PLASTERED



PLASTER FINISH ABOVE TILE WAINSCOT



FRAMES IN MASONRY PARTITION FACED WITH DRYWALL



DOUBLE EGRESS DOORS



EXPOSED MASONRY BLOCK OR BRICK

FRAMES IN MASONRY PARTITIONS



PLASTER FINISH

FRAMES IN METAL STUD NO PLASTER PARTITIONS



FRAME AT CONCRETE WALLS



STANDARD DOOR FRAME



DOUBLE EGRESS DOOR FRAME

Notes
1. See specifications for thickness of all metal.
2. Frames for sound rated doors are shown on Standard Detail No. 7B.
3. Frames for lead lined doors are shown on Standard Detail Nos. 24E, 24F & 24F1.
4. Frames for sliding doors are shown on Standard Detail No. 8A & 8B.
5. Details shown on this sheet do not cover all possible conditions. They show the basic conditions and indicate the desired relationships to adjacent surfaces.

TITLE: FRAMES FOR INTERIOR DOORS

DATE ISSUED APRIL '80 | REVISION

8

Veterans Administration STANDARD DETAIL



8A

Veterans Administration STANDARD DETAIL

FRAME FOR MANUALLY OPERATED SLIDING DOORS

TITLE

DATE ISSUED MAR. '78

REVISION

NOTES

1. TYPE & SIZE OF DOOR SHALL BE AS INDICATED ON PLANS.
2. IN MASONRY PARTITION ABOVE DOOR & ON POCKET SIDE SHALL BE CONSTRUCTED AS SHOWN OF METAL STUDS & CHANNELS.
3. PROVIDE A 12" x 24" METAL ACCESS DOOR ON CORRIDOR SIDE OF POCKET JUST ABOVE CORRIDOR BASE.
4. DETAILS FOR INSTALLATION IN DRY-WALL PART'NS. ARE SIMILAR.



SECTION "A"
DOOR HEAD AT POCKET



SECTION "C"
DOOR JAMB AT POCKET



PLAN OF DOOR POCKET
SCALE 3/4"=1'-0"



ELEVATION OF DOOR POCKET
(CORRIDOR SIDE)



SECTION "B"
DOOR HEAD



DOOR JAMB
STRIKE SIDE

NOTES

1. SEE ARCH. PLANS FOR SIZE & TYPE OF DOOR & LOCATION OF DOOR POCKET.
2. PROVIDE HORIZONTAL BRACING FOR 3/4" FURRING CHANNELS AT MID-HEIGHT OF DOOR POCKET.
3. DETAILS FOR INSTALLATION IN DRY-WALL PARTITIONS ARE SIMILAR.
4. WHERE MASONRY PARTITIONS ARE USED PARTITION ABOVE DOOR & AT POCKET SHALL BE CONSTRUCTED AS SHOWN OF METAL STUD & PLASTER.

TITLE: FRAMES FOR AUTOMATIC SLIDING DOORS

DATE ISSUED APRIL '60 | REVISION

8B

Veterans Administration STANDARD DETAIL



TYPICAL PLAN

NOT TO SCALE



BOTTOM LANDING



TYPICAL PLANS

1/4" = 1'-0"



SECTION THRU GUARD RAIL

NOT TO SCALE



ELEVATION OF WALL HAND RAIL

NOT TO SCALE



WALL HANDRAIL BRACKET DETAIL

NO SCALE

NOTES

IN ADDITION TO THE ABOVE-NOTED REQUIREMENTS, ALL HOSPITAL EXIT STAIRS SHALL CONFORM TO THE REQUIREMENTS FOR CLASS A STAIRS AS SET FORTH IN NFPA 101.

STEEL STAIR IS RECOMMENDED IN LIEU OF CONCRETE STAIR DUE TO COST.

STAIR DETAILS (EXIT STAIRS)

TITLE	REVISION
JUNE 1, 1986 DATE ISSUED	

10

Veterans Administration STANDARD DETAIL



STEEL STAIR

EXTERIOR STAIR



INTERIOR STAIR

10A

Title: STAIR TREAD & RISER DETAILS

Date Issued: 1/30/19

Revision:

Notes:



10B

Title
STEEL STAIR TO SERVICE AREA

Date Issued
1/30/89

Revision

Notes

NOTE:
PROVIDE LINTEL AT HEAD



TYPICAL MULLION



ELEVATION-MULTIPLE PANES



JAMB



TYPICAL SECTION - SILL
FRAME IN MASONRY PARTITION
W/ PLASTER FINISH -



ELEVATION - SINGLE PANE

TYPICAL ELEVATIONS



SILL
FRAME IN MET. STUD PARTITION
W/DRYWALL FINISH

NOTES
1. GLASS TYPE SHALL BE AS SPECIFIED.
2. HEIGHT MAY VERY IF NECESSARY.
3. SEE SPECS. FOR GAUGES & OTHER REQUIREMENTS.
4. IN METAL STUD PART'S., PROVIDE RUNNER C OVER WINDOW & CONTINUE STUD SPACING OVER.
5. HEIGHT OF ONE-WAY OBSERVATION WINDOWS FROM FL. TO SILL SHALL BE 2'-0" IN AREAS SUCH AS GROUP THERAPY FOR VIEWING A SITTING POSITION.
6. REMOVABLE STOP OPPOSITE PATIENTS SIDE.
7. MODIFY AS NEC. FOR INSTALLATION IN METAL STUD PART'S. WITH PLASTER FIN. SEE DR. FR. DETAIL ON STD. DETAIL NO. 8.

TITLE
OBSERVATION WINDOWS

DATE ISSUED
REVISION SEP. 14, 1966

11

Veterans Administration STANDARD DETAIL



ELEVATION
SCALE: 1/4" = 1'-0"



PLAN SCALE: 1/4" = 1'-0"



ELEVATION A-A
SCALE: 3/8" = 1'-0"



SECTION B-B
SCALE: 3" = 1'-0"

12

Title

TOILET STALL

Date issued

53 11

Revision

Notes



PLAN "A"



ELEVATION "A"

CEILING HUNG SCREEN



PLAN "B"

SCALE 1/4" = 1'-0"

12A

Title
ENTRANCE SCREEN FOR
WHEELCHAIR TOILET

Date Issued
1/3[illegible]

Revision

Notes
1. THE ABOVE PLANS REFLECT MINIMUM DIMENSIONS FOR WHEELCHAIR ENTRY.
2. PRIVATE WHEELCHAIR TOILETS DO NOT REQUIRE SCREENING.



FRONT ELEVATION



SECTION △A



PLAN



DETAIL ①

NOTES

WHERE PLAN ARRANGEMENT ALLOWS, THE ACCESS PANEL TO THE CONCEALED FLUSH VALVE IS TO BE LOCATED ON THE REVERSE SIDE OF THE PARTITION. THE BOTTOM OF THE PANEL FRAME IS TO BE 1 FT. 9 IN. ABOVE THE FLOOR. THE HORIZONTAL LOCATION SHALL REMAIN THE SAME. ACCESS PANELS OCCURING IN FIRE OR SMOKE PARTITIONS AND THE PARTITION, SHALL BE DESIGNED TO RETAIN THE REQUIRED UL FIRE RATING OF THAT PARTITION.

SELF-CARE TOILET FOR SPINAL CORD INJURY USE — PLAN & DETAILS

TITLE

DATE ISSUED Sept. '79 | REVISION MAR. '82

12B

Veterans Administration STANDARD DETAIL

ELEVATION "A"

BRACKET SEE STD. DET. 20

ELEVATION "B"

ANCHORAGE PER STD. DET. 66

PLAN

CURTAIN TRACK DETAIL

NOTES

CONSTRUCTION TO BE SIMILAR TO STD. MFGR. TOILET PARTITIONS AND/OR AS SPECIFIED. SEE STD. DET. 20 FOR DETAILS OF WOOD SEAT.

TYPICAL DRESSING BOOTHS

(NON WHEEL CHAIR)

TITLE

DATE ISSUED JUNE '78 | REVISION 4/18/80

12E

Veterans Administration STANDARD DETAIL



PLAN



ELEVATION "A"

DETAIL FOR
INTERMEDIATE SUPPORT

DRESSING ROOMS IN SPINAL CORD INJURY & GENITORY-URINARY CLINICS

NOTES

TITLE

DATE ISSUED MARCH 78 REVISION 6/36

12F

Veterans Administration STANDARD DETAIL



SCALE: 1/2"=1'-0"

3

Title
SHOWERS. PATIENT WHEELCHAIR ACCESSIBLE.

Date Issued
1/30/80

Revision

Notes
1. SEE ARCH. STD DETAIL 14-B FOR GRAB BAR DETAIL.



SCALE: 1/2"=1'-0"

3

Title
SHOWERS. PATIENT WHEELCHAIR ACCESSIBLE.

Date issued
1/30/87

Revision

Notes
1. SEE ARCH. STD DETAIL 14-B FOR GRAB BAR DETAIL



SCALE: 1/2" = 1'-0

13.1	Title: SHOWER ~~[illegible]~~ PATIENT WHEEL CHAIR ACCESSIBLE	Date issued: 1/30/79 Revision:	Notes



DETAIL 1



SECTION C-C

13.2

Title
SHOWER - PATIENT WHEEL CHAIR ACCESSIBLE.

Date Issued
1/5/89

Revision

Notes



ROUGH-IN FOR SHOWER HEAD

Title
PERSONNEL SHOWER (SINGLE USE AREA)

Date Issued
1/30/79

Revision

Notes FOR NOTES SEE "PERSONNEL SHOWER (MULTIPLE USE AREA)"



SECTION

PLAN

Notes: 1. FL & WALL FIN SHALL BE CT. UNLESS OTHERWISE NOTED 2. SEE STD DET. 14B FOR GB 3. SEE STD DET. 13 FOR PATIENT SHOWER ADDITIONAL DETAILS.

Date Issued 1/30/

Revisions

Title: PERSONNEL SHOWER (MULTIPLE USE AREA)

138

PLAN



ELEVATION



SECTION

Title
GRAB BARS & CURTAIN ROD - RECESSED TUB

Date Issued
1/31/89

Revision

Notes
SEE STD DET # GB. & CURTAIN ROD CORNER TUB.

14



FRONT ELEVATION



ELEVATION A



TOP PLATE REFLECTED PLAN



NOTE: SLOPE FLOOR TO DRAIN 1/4" PER FT. SEE FLOOR PLANS FOR EXTENT OF SLOPED AREA

PLAN



ELEVATION B



DETAIL "A" EYE BOLT SUPPORT

NOTES

1. SEE STANDARD DETAIL 14B FOR GRAB BAR ANCHORAGE.
2. FOR SPECIAL CONDITION REQUIRING FLOOR MOUNTING OF FIXTURE, OMIT CHAIR CARRIER AND ADD PEDESTAL FURNISHED BY MFGR OF BATH.
3. BEAM (4" MIN. FLANGE WIDTH) BETWEEN FLOOR DECK BEAMS OR ON TOP OF INTERSTITIAL FLOOR PURLINGS.

SCALE 0 1' 2' 1/2" = 1'-0"

SCALE 3" = 1'-0"

WALL MOUNTED SITZ BATH (PERINEAL BATH) WITH GRAB BARS

TITLE

DATE ISSUED	REVISION
6/16/86	

14A

Veterans Administration STANDARD DETAIL



CERAMIC TILE FINISH ON METAL STUDS



CERAMIC TILE FINISH ON MASONRY



EXPOSED C.M.U.



S.F.T.U. FINISH ON METAL STUDS



GRAB BAR ONE SIDE OF METAL TOILET PARTITION



GRAB BAR EACH SIDE OF METAL TOILET PARTITION



S.F.T.U SOAPS ON C.M.U. PARTITION



TYPICAL RETURN AT WALL



TYPICAL INTERMEDIATE SUPPORT

NOTES

GRAB BARS SHALL BE THRU WELDED TO FLANGES. EXPOSED EDGE OF FLANGES SHALL BE SLIGHTLY ROUNDED.

Reinforcement for grab bars to be according to manufacture's recommendations.

GRAB BAR ANCHORAGE

TITLE

DATE ISSUED APRIL '80 REVISED

1A B

Veterans Administration STANDARD DETAIL



SECTION "A - A"



ELEVATION

NOTES

1. PRECISE LOCATION OF SUSPENSION TRACKS SHALL BE DETERMINED BY THE DEPARTMENT OF MEDICINE & SURGERY FOR EACH SPECIFIC PROJECT.

TRAPEZE, EXERCISE BAR & PATIENT HELPER SUSPENSION TRACK FOR SITZ BATH

TITLE

DATE ISSUED APR 80 | REVISION

14C

Veterans Administration STANDARD DETAIL



DETAIL-1

DETAIL-2

NOTES TO ARCHITECT

1. REVISE DETAIL NO. 1 IF SHOWING THE UNDERSIDE OF CONCRETE RIBS OR STEEL FRAMING.
2. THE A/E TO PROVIDE DETAILS OF SUPPORT WHERE "INTERSTITIAL SPACE" OCCUR.



S.C.I. SELF CARE WATER CLOSET



FRONT ELEVATION OF PATIENT LITTER SHOWER

FRONT ELEV. OF W/C SHOWER

SEE STD. DETAIL NO. 13

S.C.I. SHOWER

NOTES

1. FRAME BRACING TO BE FURNISHED AND INSTALLED BY CONTRACTOR.
2. TRAPEZE TO BE FURNISHED AND INSTALLED BY VETERANS ADMINISTRATION.

TRAPEZE ELEV. TYP. LOCATIONS & BRACING DETAILS

TITLE

DATE ISSUED DEC '79 REVISION 5/29/80

14D

Veterans Administration STANDARD DETAIL



TYP. EL. OF TRAPEZE
AT SCI SHOWER ROOMS

SIDE ELEVATION OF TRAPEZE (A)
AT S.C.I. SELF CARE TOILET

NOTES TO ARCHITECT
1. REVISE DETAIL TO SHOW THE UNDERSIDE OF CONCRETE RIBS OR STEEL FRAMING.
2. THE A/E TO PROVIDE DETAILS OF SUPPORT WHERE "INTERSTITIAL SPACE" OCCUR.

Deleted 7/7/1



TYP. EL. OF TRAPEZE
AT TREATMENT & EXAMINATION



PLAN
EXAMINATION TABLE

NOTES
1. SEE 1/4" SCALE ELEVATIONS FOR LOCATING TRAPEZE.
2. FRAME BRACING TO BE FURNISHED AND INSTALLED BY CONTRACTOR.
3. TRAPEZE TO BE FURNISHED AND INSTALLED BY VETERANS ADMINISTRATION.

TITLE: TRAPEZE FRAMING ANCHORAGE & DIMENSIONS

DATE ISSUED DEC. 79 | REVISION 5/22/80

14E
Veterans Administration STANDARD DETAIL



SCALE: 3"=1'-0"

PLAN



SKETCH
(NOT TO SCALE)



PLAN OF TOILET AREA SHOWING RELATIONSHIP TO FIXTURES

SCALE: 1/4"=1'-0"

Veterans Administration Standard Detail

14

Title
STANDARD GRAB BAR FOR WATER CLOSET IN NURSING HOME

Date Issued
1/30/89

Revision

Notes



PLAN SHOWING THE STEEL TUBE & PLATE FOR ANCHORING THE UP-SWING GRAB BAR

SCALE: ½" = 1'-0" UNLESS OTHERWISE NOTED.



1/4" = 1'-0"

PLAN OF TOILET ROOM SHOWING RELATIONSHIP OF FIXTURES



ELEVATION SHOWING POSITION OF UP-SWINGING GRAB BAR



SIDE ELEVATION OF UP-SWING GRAB BAR

Veterans Administration Standard Detail

14G

Title
UP-SWINGING GRAB BAR FOR WATER CLOSET OF NURSING HOME

Date Issued

Revision

Notes



ELEVATION
TYPICAL LAV AND MIRROR.



ELEVATION
TYPICAL WH/C LAV AND MIRROR

SIDE ELEVATION
TYPICAL WH/C LAV AND MIRROR

SCALE 3/4" = 1'-0"

5

Title
LAVATORY - WHEELCHAIR AND STANDARD

Date Issued
1/30

Revision

Notes
1. ALTERNATE LOCATION FOR SHELF WHEN WH/C LAV NOT LOCATED ADJACENT TO WING WALL.
2. SEE STD. DET. 15A FOR DETAIL OF SHELF & FILLER PLATE BEHIND LARGE MIRROR.



FRONT ELEVATION



SIDE ELEVATION



PLAN

Deleted 7/87

NOTES

1. KEEP HOT & COLD WATER LINES & REQUIRED KEY STOPS ABOVE C OF WASTE.

WHEELCHAIR LAV. FOR SPINAL CORD INJURY UNITS

TITLE

DATE ISSUED Sept. '79 | REVISION June '82

15A Veterans Administration STANDARD DETAIL



SECTION A-A
NO SCALE



PLAN
NO SCALE

NOTE

AT LAVS WITH FOOT PEDAL CONTROLS PROVIDE AN ADDITIONAL 16 GA. GALV. STEEL PLATE 12" X 18" SECURED TO A MIN. OF 2 STUDS

NOTES

THIS SUPPORT IS TO BE USED FOR ALL 400 SERIES LAVS, EXCEPT P-410, P-412, & P-413, ON METAL STUD PARTITIONS.

TITLE: LAVATORY SUPPORT

DATE ISSUED 6/16/86 | REVISION

15B

Veterans Administration STANDARD DETAIL



FULL SIZE DETAIL OF FILLER PLATE



SIDE-WALL-MOUNTED 6"x18" S/S SHELF
SCALE: 1½" = 1'-0"



BACK-WALL-MOUNTED 5"x17" S/S SHELF
SCALE: ½" = 1'-0"

15.1

Title
LAVATORY DETAILS
WHEELCHAIR & STANDARD.

Date Issued
1/31/89

Revision

Notes



PLAN



PLAN

NOTES

NOTE TO ARCHITECT

ARCHITECT SHALL FULLY DETAIL CONSTRUCTION FOR EACH INDIVIDUAL PROJECT.

HOUSEKEEPING AID CLOSET

TITLE

DATE ISSUED JAN. 80

REVISION 12/1/80

18

Veterans Administration STANDARD DETAIL



CERAMIC TILE FINISH ON METAL STUD PARTITION



CERAMIC TILE FINISH ON MASONRY PARTITION



C.M.U. EXPOSED FINISH



ELEVATION OF END OF RAIL AND BRACKET



PLAN OF TYPICAL END

NOTE:
1. BRACKETS FOR STAIN. STEEL RAILING SHALL BE SPACED AT 4'-0" MAXIMUM O.C.
2. SEE PLANS FOR LOCATION OF WALL RAILING.
3. PROVIDE PROPER METAL SPACERS AND TOGGLE BOLTS OR EXPANSION BOLTS WHERE APPLICABLE.
4. FOR THERAPEUTIC POOL DETAILS, SEE STD. DETAIL Nº 47.

RAILING AT WALLS OF THERAPEUTIC POOL EXERCISE ROOM

JAN.'76

19A

VA ARCHITECTURAL STANDARD DETAIL



ELEVATION OF WALL SEAT



FREE STANDING BENCH



SECTION THRU SEAT

NOTES

SEATS IN DRESSING AREAS

TITLE

DATE ISSUED MARCH '78 | REVISION 4/29/80

20 Veterans Administration STANDARD DETAIL



ELEVATION OF WALL SEAT



SECTION THRU WALL SEAT



NOTE: 4"x⅜" METAL CLEATS SHALL BE FASTENED TO UNDERSIDE OF WOOD SEAT WITH 1½" N°10 R.H. WOOD SCREWS 2'-0" O.C. STAGGERED. RECESS METAL CLEATS FLUSH WITH BOTTOM OF SEAT.

DETAIL "W" ON METAL STUD PARTITION



DETAIL "X" ON METAL STUD PARTITION



DETAIL "W" ON EXPOSED MASONRY PARTITION (PLASTER FIN. AS NOTED)



DETAIL "X" ON EXPOSED MASONRY PARTITION

NOTES

1. SEE SHEET NO. 20 FOR WOOD SEATS IN SHOWER STALLS AND DRESSING BOOTHS.
2. PROVIDE SLOTTED HOLES FOR WOOD SCREWS.
3. FOR ANCHORAGE TO OPEN CELL BLOCK, USE TOGGLE BOLTS. FOR ANCHORAGE INTO WEB OF BLOCK, USE EXPANSION BOLTS.

TITLE: SEATS IN DRESSING & LOCKER ROOMS AND THERAPEUTIC POOL

DATE ISSUED | REVISION

20 A

Veterans Administration STANDARD DETAIL



SECTION 1-1



SECTION 4 - 4
TYPICAL SECTION THRU
FRAME OF BULLETIN BOARD



ELEVATION WITH SLIDING DOORS



ELEVATION WITH HINGED DOORS

TYPICAL ELEVATIONS



SECTION 2-2



NOTE: FOR SIZE SEE NOTES

ELEVATION OF CHALKBOARD



SECTION 3 - 3



NOTE: FOR SIZE SEE NOTES

ELEVATION OF BULLETIN BOARD

TYPICAL ELEVATIONS

ALUMINUM FRAMED CHALKBOARDS AND BULLETIN BOARDS



SECTION A - A (SLIDING DOORS)

SECTION B - B

SECTION C - C (HINGED DOORS)

SECTION D - D

ALUMINUM FRAMED BULLETIN BOARDS WITH GLASS DOORS

NOTE :

1. SIZE OF BULLETIN BOARD AS INDICATED ABOVE EXCEPT AS OTHERWISE NOTED.
2. SEE ARCHITECTURAL PLANS FOR LOCATION AND SIZE OF CHALKBOARDS AND BULLETIN BOARDS. SIZES GIVEN WILL BE ACTUAL BOARD SIZE.
3. PROVIDE MAP HOOK RAIL AND MAP HOOKS ON CHALKBOARDS IN CLASS ROOMS, CONFERENCE ROOMS AND EDUCATIONAL THERAPY.
4. OMIT MAP HOOK RAIL ON CHALKBOARDS IN LABORATORIES.
5. SEE SPECIFICATIONS FOR MATERIALS AND METHODS OF FASTENING TO WALLS.

NOTES

TITLE: CHALKBOARDS AND BULLETIN BOARDS

DATE ISSUED APRIL '60 REVISION

21

Veterans Administration STANDARD DETAIL

RADIOGRAPHIC ROOM

(PATIENT ACCESS TO THIS SIDE OF TABLE)

R/F ROOM

(PATIENT ACCESS TO THIS SIDE OF TABLE)

PLANS

SCALE: 1/4" = 1'-0"

SECTION

TYPICAL FLOOR DUCT

SECTION

DETAIL FOR BOLTING EQUIPMENT TO STRUCTURAL SLAB WHERE REQUIRED OVER DUCT COVERPLATE

NOTES

X-RAY FLOOR DUCT FOR CABLES TO EQUIPMENT

TITLE

DATE ISSUED	REVISION
JAN. 81	JUN. 4,

22

Veterans Administration STANDARD DETAIL

	ROOM	LEAD IN PARTITIONS (IN M.M.)	LEAD IN DOORS & CONTROL WINDOWS (IN M.M.)	LEAD ON FLOOR SLAB (IN M.M.)	LEAD ON CLG. SLAB (IN M.M.)	HEIGHT OF LEAD IN PARTITIONS	REQUIRED FL. DEPRESSIONS (SEE NOTES)
1.	RADIOGRAPHIC FLUOROSCOPIC ROOM (CEILING MOUNTED X-RAY), SPECIAL PROCEDURES DIAGNOSTIC AND TELE-FLUOROSCOPY (CLG. MTD. X-RAY)	1.5 IN 4" BLOCK PART'N. 2.15 ON MET. STUD PART'N 3.0 DARK RM. SIDE.	2.15 (3.0 FOR DOOR TO DARK ROOM).	1.5 ON 2½" MIN. SOLID SLAB NONE ON 4½" MIN. SOLID SLAB.	NONE	7'-0" *	3½" WITH OR WITHOUT LEAD.
2.	DEEP THERAPY { CONVENTIONAL, COBALT, BETATRONS, LINEAR ACCELERATORS.	← SHIELDING AS DETERMINED BY A PHYSICIST					→
3.	CYSTOSCOPIC ROOM.	1.5 IN 4" BLOCK PART'N 2.15 ON MET. STUD PART'N 3.0 DARK RM. SIDE.	2.15	1.5 ON 2½" MIN. SOLID SLAB NONE ON 4½" MIN. SOLID SLAB.	NONE	7'-0" *	3½" WITH LEAD 1" WITHOUT LEAD. * *
4.	ANIMAL - X-RAY, ANIMAL - RESEARCH, RADIOGRAPHY & FLUOROSCOPY.	1.5 IN 4" BLOCK PART'N. 2.15 ON MET. STUD PART'N.	2.15 (3.0 FOR DOOR TO DARK ROOM).	1.5 ON 2½" MIN. SOLID SLAB NONE ON 4½" MIN. SOLID SLAB.	NONE	7'-0" *	1" * *
5.	DENTAL X-RAY AREA (STATIONARY WALL MOUNTED 90/100 KVP X-RAY) - (STATIONARY PANORAMIC X-RAY), ORAL SURGERY RM. (WHEN INDICATED BY DM&S) - (STATIONARY CEILING MOUNTED 65/90/100 KVP X-RAY) GENERAL TREATMENT OPERATORIES (WHEN INDICATED BY DM & S) STATIONARY CEILING MOUNTED 65/90/100 KVP	1.0 (CONC. BLOCK OR MET. STUD)	1.0MM	NONE	NONE	7'-0" *	1" * *
6.	DENTAL X-RAY (PORTABLE 60/65 KVP)	NONE	NONE	NONE	NONE	NONE	NONE
7.	FLUOROSCOPIC RMS. VERTICAL OR TILT TYPE GASTROENTEROLOGY (NO RADIOGRAPHY).	1.5 IN 4" BLOCK PART'N. 2.15 ON MET. STUD PART'N. (NO CONTROL BOOTH REQ'D.)	2.15	1.5 ON 2½" MIN. SOLID SLAB NONE ON 4½" MIN. SOLID SLAB.	NONE	7'-0" *	1" FOR VERT. TYPE & 3½" FOR TILT TYPE FLUOROSCOPE.
8.	OPERATING ROOM INCLUDING ANIMAL OPERATING (PORTABLE X-RAY), CARDIAC AND NEUROSURGICAL OPERATING ROOM (PORTABLE X-RAY).	NONE EXCEPT 3.0 ON DARK RM. SIDE.	NONE EXCEPT 3.0 FOR DOOR TO DARK RM.	NONE	NONE	NONE *	1" * *
9.	CARD. CATHETERIZATION IN CARDIO-PULMONARY CLINIC (CEILING MOUNTED X-RAY), OPERATING ROOM CLG. MOUNTED X-RAY & COMPUTERIZED TRANS-AXIAL TOMAGROPHY X-RAY.	1.5 IN 4" BLOCK PART'N. 2.15 ON MET. STUD PART'N. 3.0 DARK RM. SIDE.	2.15 (3.0 FOR DOOR TO DARK ROOM).	1.5 ON 2½" MIN. SOLID SLAB NONE ON 4½" MIN. SOLID SLAB.	NONE	7'-0" *	3½" WITH OR WITHOUT LEAD.
10	ULTRASOUND & THERMOGROPHY.	NONE	NONE	NONE	NONE	NONE	NONE

NOTES:

1. THE STRUCTURAL REQUIREMENTS RELATING TO X-RAY RADIATION PROTECTIVE BARRIERS ARE TO BE IN COMPLIANCE WITH NATIONAL COUNCIL ON RADIATION PROTECTION AND MEASUREMENTS PUBLISHED REPORTS NOS. 33 & 34.
2. FLOOR DEPRESSIONS NOTED ARE TO PROVIDE SPACE FOR ELECTRICAL CONDUITS, RACEWAYS, JUNCTION BOXES, ETC.; TO PROVIDE COVER FOR LEAD SHIELDING; AND TO PROVIDE FOR LEVEL FLOOR.
3. SEE OTHER STANDARDS FOR DETAILS OF LEAD IN FLOORS, PARTITIONS AND DOORS
4. LEAD THICKNESS MAY VARY FOR SPECIAL CONDITIONS.
5. PROVIDE ADDITIONAL LEAD ON SLAB WHERE REQUIRED FOR X-RAY EQUIPMENT.
6. * LEAD IN PARTITION ADJACENT TO, FACING, OR IN NEAR PROXIMITY TO DARK ROOM SHALL EXTEND TO CEILING.
7. * * WHERE OVERALL TOPPING OR FILL IS PROVIDED ON SLAB, DISREGARD THIS DIMENSION.
8. ALL SHIELDING REQUIREMENTS SHALL BE REVIEWED BY RADIOLOGY SERVICE, DEPT. OF MEDICINE AND SURGERY, VETERANS ADMINISTRATION.

NOTES

LEAD LINING IN X-RAY ROOMS

(TO BE USED AS A PRELIMINARY GUIDE ONLY)

TITLE

DATE ISSUED APRIL '80 | REVISION

24

Veterans Administration STANDARD DETAIL



BOTTOM OF TYPICAL PART'N WITH RACEWAYS IN FLOOR



PLAN OF DEEP PIPE CHASE



DETAIL AT INTERIOR COLUMN



PLAN OF 90° ANGLE CORNER



TYPICAL JOINT IN LEAD ON SLAB



PLAN OF SHALLOW PIPE CHASE



BOTTOM OF PARTITION DEEP THERAPY



OPTIONAL LEAD LAP AT JOINTS IN DEEP THERAPY PART'N



LEAD PART HEIGHT
LEAD FULL HEIGHT
TOP SECTION OF PARTITIONS



BOTTOM SECTION TYPICAL PARTITION



PLAN OF OBTUSE ANGLE CORNER



PLAN OF INTERSECTION

NOTES

1. FURRING AROUND COLUMNS, DUCTS, ETC., TO BE LEAD LINED EXCEPT IN EXTERIOR WALLS.
2. THICKNESS OF LEAD IN PARTN'S AND ON FL. SLAB TO BE GOVERNED BY RM REQUIREMENTS.
3. IN DEEP THERAPY EXTEND LEAD 1'-0" OUTSIDE OF PARTN'S WHEN LEAD STRIP IS UNDER PARTN'S.
4. WHERE LEAD LINED PARTN'S IN DEEP THERAPY ABUT COL., EXTEND LEAD ACROSS ENTIRE FACE OF COL.
5. LEAD ON CEILING SLAB OF DEEP THERAPY SHALL EXTEND 1'-0" OUTSIDE OF LEAD LINED PARTN'S.
6. THIS DETAIL NOT TO BE USED FOR SEISMIC AREAS. USE METAL STUD PARTN'S W/ LEAD BACKED GYP. WALLBRD.

LEAD LINED BLOCK PARTITIONS IN NEW CONSTRUCTION

INTERIM COPY

TITLE

DATE ISSUED APRIL 20 | REVISION

244

Veterans Administration STANDARD DETAIL



PLAN-EXTERNAL CORNER



PLAN-INTERNAL CORNER



PLAN "B" AT COLUMN



LEAD LAP AT JOINT IN LATH

METHOD OF INSTALLING LEAD LINED LATH



PLAN "A" AT COLUMN



LEAD SLAB TO SLAB
OCCURS AT DENTAL X-RAY & DEEP THERAPY



TYPICAL JOINT IN LEAD ON SLAB

NOTE:
1. SEE STD. DETAIL No. 24 "LEAD LINING IN X-RAY ROOMS" FOR LOCATIONS WHERE LEAD AND/OR RACEWAYS ARE REQUIRED IN FLOOR.
2. SEE PLANS AND FINISH SCHEDULE FOR WALL FINISH AND ROOM BASE.
3. FURRING PARTITIONS AT COLUMNS, PIPES, DUCTS ETC. SHALL BE LEAD LINED UNLESS OTHERWISE NOTED ON PLANS.
4. THICKNESS OF LEAD IN PARTITION & FLOOR GOVERNED BY ROOM REQUIREMENTS. (SEE PLANS & STD. DETAIL No. 24.)
5. SEE STD. DETAILS No. 18 AND 24 AND STRUCTURAL DRAWINGS FOR DEPRESSED SLABS AND BEAMS.
6. SEE DETAILS OF LEAD-LINED DOORS FOR LEAD STRIP IN FLOOR AT DOOR OPENINGS.

TITLE: LEAD LINED METAL STUD PARTITION IN NEW CONSTRUCTION

DATE ISSUED APRIL '80 | REVISION | INTERIM COPY

24B
Veterans Administration STANDARD DETAIL







METAL STUD PARTITION WITH LEAD ON FLOOR
(PLASTER WALL FINISH)



METAL STUD PARTITION WITH OR WITHOUT LEAD ON FLOOR OF ROOM
(CERAMIC TILE WALL FIN.)

METAL STUD PARTITION WITH 1.0MM. OR LESS LEAD
(PLASTER WALL FINISH)



METAL STUD PARTITION WITH 1.0MM. OR LESS LEAD
(CERAMIC TILE WALL FIN.)

MASONRY PARTITION WITH LEAD ON FLOOR
(PLASTER WALL FINISH)



MASONRY PARTITION WITH OR WITHOUT LEAD ON FLOOR OF ROOM
(CERAMIC TILE WALL FIN.)



METAL STUD PARTITION WITH OVER 1.0MM LEAD & NO LEAD ON FLOOR
(PLASTER WALL FINISH)



TYPICAL JOINT IN FLOOR LEAD



MASONRY PARTITION WITHOUT LEAD ON FLOOR
(PLASTER WALL FINISH)

NOTES

1. THICKNESS OF LEAD SHALL BE DETERMINED BY ROOM REQUIREMENTS.
2. SEE FIN. SCHEDULE FOR ROOM FINISH.
3. WOOD FURRING STRIPS SHALL BE SECURED TO METAL STUDS OR MASONRY AS SPECIFIED.
4. ALL WOOD FURRING STRIPS TO BE FIRE TREATED.
5. THESE DETAILS ARE NOT APPLICABLE TO DEEP THERAPY ROOMS.

LEAD LINING FOR PARTITIONS AND FLOORS IN EXISTING BUILDING

TITLE

DATE ISSUED APRIL '80 | INTERIM COPY | REVISION

240

Veterans Administration STANDARD DETAIL



HEAD-LEAD LINED BLOCK
(JAMB SIMILAR EXCEPT AS NOTED)
LEAD LINED ROOM SIDE

RABBET DIM. VARIES AS REQUIRED FOR DOOR THICKNESS * (SEE NOTE)



JAMB-HEAD SIMILAR- DOOR & FRAME
IN LEAD LINED METAL STUD PARTITION



JAMB-HEAD SIMILAR
FRAME FOR DOORS 3'-2" & LESS
NOTE:- TO PROVIDE ANGLE LINTEL FOR PLASTER WALLS

NOTES
1. SECURE SURFACE PIVOTS TO DR. W/ 5-5/16" O.H. CSK BOLTS & TO FRAME W/ 4-5/16" O.H.M.S. CSK NUT ENDS OF BOLTS & COVER W/ 3"X6" LEAD LINED PAN SECRD. TO DR. W/6-NO.10 R.H. 3/4 W.S.
2. THICKNESS OF LEAD & LEAD GLASS IN DRS. & LEAD IN PARTN'S & FLS. GOVERNED BY RM REQUIREMENTS.
3. LEAD IN HEAD SECTION IS NOT REQUIRED WHERE LEAD IN PARTN IS ONLY 7'-0" HIGH.
4. SPECIAL ANCHORAGE OF JAMB STRUCTURAL ANGLES & PLATES AT INTERSTITIAL SPACE MAY BE NEEDED, SEE PLANS.

* NOTE ON DRAWINGS
CONTRACTOR TO COORDINATE RABBET DIM. WITH THICKNESS OF DOOR APPROVED.



TYPICAL (DEPRESSED) SILL



RAISED SILL (FOR USE IN ALTERATION PROJECTS)



ELEVATION

LEAD GLASS VISION PANEL

RAYPROOF LIGHTPROOF LOUVER

NOTE:- SEE PLANS FOR DOOR SWINGS

LEAD LINED DOOR
TYPE 15 & FRAME
(MEDIUM X-RAY PROTECTION)

TITLE

DATE ISSUED APRIL '80 | REVISION

24F
Veterans Administration STANDARD DETAIL

NOTE: FOR LEAD STRIP UNDER DOOR AT ROOM(S) WITHOUT LEAD IN FLOOR, SEE STD. DETAIL No. 24E



TYPICAL SECTION THRU THRESHOLD





SECTION C-C



SECTION B-B

ELEV. OF DOOR



SECTION A-A

NOTES

1. LEAD THICKNESS SHALL BE AS DETERMINED BY A PHYSICIST.
2. WIDTH OF DOOR FRAME VARIES WITH ROOM FINISHES & DOOR THICKNESS.
3. LEAD STRIP SHOWN AT EDGE OF DOOR IS REQUIRED AT ALL FOUR EDGES.
4. REFER TO PLANS FOR RIGHT OR LEFT HAND DOOR SWING.
5. DO NOT USE THIS DETAIL IN SEISMIC AREAS. USE LEAD LINED DOOR FRAME IN LEAD LINED METAL STUD PARTITION ST. DETAIL NO. 24F1.

LEAD LINED DOOR TYPE 17 & FRAME

(IN LEAD LINED CMU WALLS)

TITLE

DATE ISSUED	REVISION
APRIL '80	

24F

Veterans Administration STANDARD DETAIL

NOTE: FOR LEAD STRIP UNDER DOOR AT ROOMS WITHOUT LEAD IN FLOOR. SEE STD. DET. NO. 24E

FACE OF MASONRY

4-3/8" F.H.CSK. EXP. BOLTS THRU SEPARATORS 12" O.C. STAGGERED

1'-0"

2"

11GA. STEEL THRESH

FIN. FLOOR

2 1/4"

DOOR FRAME

1/4" DOOR CLEARANCE

FILL WITH GROUT

LAP

DEPTH AS SCHEDULED 6

LEAD ON FLOOR IN SHIELDED ROOMS AS SCHEDULED

LEAD STRIP UNDER PARTITION AND ACROSS OPENINGS

1/2" CEM. GROUT TOP OF SLAB

TYPICAL SECTION THRU THRESHOLD

PLASTER

"V" GROOVE

6" x 3 1/2" x 1/2" L

SEE NOTE 2

CEILING HEIGHT AS REQD.

METAL STUD DIM.

LEAD LINED GYP LATH

GYP BD. OR OTHER FIN REQD

FILLER STRIP

C TYPE METAL STUDS

CASING BEAD

LEAD

1/2 GA. Z CLIPS 4 PER JAMB WELD TO FRAME AND BOLT TO STUDS

WELD

1/4" BENT PL. C

1 1/2"

4 3/4" ± (SEE NOTE N° 2)

AS REQUIRED FOR DOOR THICKNESS (SEE NOTE N° 2)

POURED LEAD DOWELS APPROX. 8"-0 C EACH WAY

LEAD PLATE IN S/S PAN CLOSURE TO COVER BOLTS OF DOOR OPERATOR ARM.

SECTION B-B

BOTTOM OF SLAB

CLIP ANGLES

BENT PLATE CHANNEL & ANGLE FRAME SLAB TO SLAB

AUTOMATIC DOOR OPERATOR & COVER

ARM & LINK

HINGE

LEAD LINED DOOR

WIDTH OF DOOR SEE ARCH. PLANS

HINGE

DOOR PULL

7'-0"

LEAD DOWELS APPROX. 8" O.C. EACH WAY.

HINGE

TOP OF SLAB

CLIP ANGLES

FIN. FL.

10" 5" EQUAL 5" 5" EQUAL 10"

CAULK 1/4" MAX.

NOTE: PROVIDE CLIP ANGLES AT TOP AND BOTTOM OF BOTH ANGLE AND CHANNEL FRAME TO ANCHOR TO FL. & CONSTRUCTION ABOVE

ELEV. OF DOOR

1/4" MAX

CAULK

GYP BOARD OR OTHER FIN AS REQUIRED

CASING BEAD

1/4" MAX

1 1/2"

METAL STUD DIMENSION

METAL STUDS CHANNEL TYPE

SEE NOTE No. 2

WELD

*12 GA. Z CLIPS 4 PER JAMB WELD TO FRAME AND BOLT TO METAL STUDS

LEAD LINED GYP. LATH

WOOD FILLER STRIP

"V" GROOVE PLASTER 6" x 3 1/2" x 1/2" L

3 1/2" ±

1/4"

8" ±

1/2" F.H.M.S. CSK.

6"

HINGE

3'-10" MAX. WIDTH OF DOOR

SECTION D-D

1/4" BENT PLATE

GYP BD.

6" x 3 1/2" x 1/2"

LEAD LINED GYP.

STUD

CLIP

CLIP

STUD

LEAD

1 1/4"

ME ST

"V" GROOVE

CHANNEL & ANGLE FRA SLAB TO SLAB SEE DET. SECT. D-D

SECTION C-C

SEE NOTE N°2

POURED LEAD DOWELS APPROX. 8"-0.C. EACH WAY

7/8" LEAD PLATE IN 7" x 5" S/S PAN CLOSURE OVER EACH HINGE SECURED TO DOOR WITH 6 NO. 10 R.H. 2 1/4" W.S.

AS REQUIRED FOR DOOR THICKNESS * (SEE NOTE N° 2)

1 7/8"

LEAD

1/2" MAX.

1/2" O.H. CSK. BOLTS

STEEL THRESHOLD

DOOR PULL

1/8"

(SEE NOTE N° 2)

METAL STUDS

Z CLIPS WELD TO FRAME (SEE SECT. D-D)

WELD

WOOD FILLER STRIP

LEAD

LEAD

1 1/2"

6" x 3 1/2" x 1/2" L

LEAD LINED GYP. LATH

"V" GROOVE PLASTER

AS REQUIRED FOR DOOR THICKNESS (SEE NOTE No. 2)

DOOR PULL

SECTION A-A

NOTES

1. LEAD THICKNESS SHALL BE AS DETERMINED BY A PHYSICIST.
2. WIDTH OF DOOR FRAME VARIES WITH ROOM FINISHES & DOOR THICKNESS.
3. LEAD STRIP SHOWN AT EDGE OF DOOR IS REQUIRED AT ALL FOUR EDGES.
4. REFER TO PLANS FOR RIGHT OR LEFT HAND DOOR SWING.

LEAD LINED DOOR TYPE 17 & FRAME IN LEAD LINED METAL STUD PARTITION)

TITLE

DATE ISSUED APRIL '50

REVISION

24 FI

Veterans Administration STANDARD DETAIL



TELESCOPING LEAD LINED FRAME IN STUD PARTITION (LEAD LINED BLOCK SIMILAR)



HEAD-JAMB SIMILAR



WINDOW ELEVATION



SILL

LEAD FRAME IN STUD PARTITION (LEAD LINED BLOCK SIMILAR)



TYP. PLAN OF CONTROL ROOM BETWEEN TWO RADIOGRAPHIC-FLUOROSCOPIC ROOMS

NOTES

1. THICKNESS OF LEAD IN PARTITION AND THICKNESS OF LEAD GLASS SHALL BE GOVERNED BY LEAD REQUIREMENT FOR EACH X-RAY ROOM.
2. SEE SPECIFICATIONS FOR LIGHT PROOF SHADE REQUIREMENTS.

TITLE: X-RAY CONTROL WINDOWS

DATE ISSUED APRIL '60 REVISIO

24 G

Veterans Administration STANDARD DETAIL



JAMB SECTION A–A (HEAD SIMILAR)

(IN LEAD LINED METAL STUD FRAMING)

SILL SECTION B-B

(IN LEAD LINED CONC. BLOCK PARTITION)



JAMB SECTION A–A (HEAD SIMILAR)

(IN NON-LEAD LINED METAL STUD PARTITION)

SILL SECTION B-B

(IN NON-LEAD LINED METAL STUD PARTITION)



NOTES

1. CASSETTE TRANSFER CABINET SHALL BE LEAD LINED WHERE OCCURRING IN LEAD LINED PARTITIONS.
2. THICKNESS OF LEAD GOVERNED BY ROOM REQUIREMENTS.
3. FOR WALL CONSTRUCTION DETAILS SEE STANDARD DETAILS FOR LEAD LINED PARTITIONS.
4. MODIFY NECESSARY FOR INSTALLATION WITH DRYWALL FINISH-SEE DOOR FRAME DETAILS ON STANDARD DETAIL NO. 8.

TITLE: CASSETTE TRANSFER CABINET

DATE ISSUED: AUG 1980 — INTERIM COPY — REVISION

24H

Veterans Administration STANDARD DETAIL



ELEVATION



PLAN

CONDUIT PIPE CHASE OPNG.
IN FLOOR



CONDUIT OPENING IN WALL



SERVICE BOX OR DUCT OPENING
IN WALL



SERVICE BOX OR DUCT OPENING
IN WALL



SERVICE BOX OR DUCT OPNG.
IN WALL



DUCT OPENING IN WALL
AT CEILING

NOTES

DETERMINATION IS MADE BY A RADIATION CONSULTANT AS TO THE THICKNESS AND HEIGHT OF LEAD SHIELDING IN WALLS TO FORM A BARRIER AGAINST LEAKAGE OF RADIATION.

TYPICAL DIAGRAMIC DETAILS FOR LEAD SHIELDING (SECONDARY PROTECTION)

TITLE

DATE ISSUED JULY 1969 | REVISION

24J
Veterans Administration
STANDARD DETAIL

MILLIMETERS	DECIMALS OF AN INCH	FRACTIONS OF AN INCH	LBS. PER SQ. FT.	LEAD GLASS EQUIVALENT
0.396	0.0156	1/64"	1	1 PLY APPROX. 1/4"
0.792	0.0312	1/32"	2	"
1.000	0.0391	5/128"	2½	"
1.191	0.0469	3/64"	3	"
1.587	0.0625	1/16"	4	"
1.984	0.0781	5/64"	5	"
2.380	0.0937	3/32"	6	"
3.175	0.1250	1/8"	8	2 PLY APPROX. 1/2"
3.967	0.1562	5/32"	10	"
4.763	0.1875	3/16"	12	3 PLY. APPROX. 3/4"
5.555	0.2187	7/32"	14	"
6.350	0.2500	1/4"	16	4 PLY. APPROX. 1"
7.142	0.2812	9/32"	18	"
8.465	0.3333	1/3"	20	5 PLY. APPROX. 1¼"
9.525	0.3750	* 3/8"	24	"
10.160	0.4000	2/5"	22½	6 PLY APPROX. 1½"
10.317	0.4062	13/32"	20	5 PLY. APPROX. 1¼"
11.112	0.4375	* 7/16"	28	7 PLY APPROX. 1¾"
12.700	0.5000	1/2"	30	"
14.287	0.5625	* 9/16"	34	8 PLY APPROX. 2"
15.875	0.6250	5/8"	38	9 PLY APPROX. 2¼"
16.934	0.6667	2/3"	40	"
19.050	0.7500	* 3/4"	44	10 PLY APPROX. 2½"
20.637	0.8125	* 13/16"	48	11 PLY APPROX. 2¾"
22.225	0.8750	7/8"	52	12 PLY APPROX. 3"
25.400	1.0000	1"	60	14 PLY APPROX. 3¼"

24K

Veterans Administration STANDARD DETAIL

LEAD SHEET THICKNESSES AND WEIGHTS

TITLE

DATE ISSUED July '69

REVISION 4/30/20

NOTES

SHEET LEAD IN ABOVE TABLE GIVEN IN COMMERCIAL THICKNESSES EXCEPT AS NOTED.

* THESE SPECIAL THICKNESSES MAY BE ROLLED IF IN SUFFICIENT QUANTITY.



Veterans Administration STANDARD DETAIL

25

CHANCEL PLAN
(SCHEMATIC)

TITLE

DATE ISSUED JULY '69

REVISION

NOTES

1. WHERE PREDELLA MUST BE OMITTED DUE TO LIMITED SPACE, LOCATE CHANCEL FLOOR 12" ABOVE FLOOR OF NAVE AND PROVIDE TWO STEPS AS SHOWN ABOVE.
2. SEE DRAWING NO. 25A FOR DETAILS OF ALTAR AND COMMUNION RAIL.
3. SEE DRAWING NO. 25B FOR DETAILS OF ARK AND ALTERNATE DETAILS OF PREDELLA.



TYPICAL ALTAR PLAN



ELEVATION ①



ELEVATION ②



SECTION A



TYPICAL ELEVATION OF RIGHT COMMUNION RAIL - LOOKING TOWARD CHANCEL



SECTION B



SECTION C



SECTION 2-2
COMMUNION RAIL WHERE CHANCEL FLOOR IS 12" ABOVE FLOOR OF NAVE



DETAIL E-E



SECTION 1-1
COMMUNION RAIL WHERE CHANCEL FLOOR IS 6" ABOVE FLOOR OF NAVE

NOTES

CHANCEL DETAILS
(ALTAR & COMMUNION RAIL)

INTERIM COPY

DATE ISSUED	REVISION
APRIL '80	

TITLE

25A

Veterans Administration STANDARD DETAIL



SECTION AT (4)



PART ELEVATION SHOWING ARK
SCALE: 1/4" = 1'-0"



PART PLAN SHOWING ARK



SECTION AT (3)

NOTES

CHANCEL DETAILS (ARK AND PREDELLA)

TITLE

DATE ISSUED APRIL '80 | INTERIM COPY | REVISION

25B

Veterans Administration STANDARD DETAIL



NOTE: ALL DOORS AND DRAWER FRONTS IN THIS ASSEMBLY SHALL BE FLUSH.



SECTION A-A



FRONT ELEVATION

R&S TYPE 1
(WARDROBE, VESTMENT AND STORAGE ASSEMBLY)



ELEVATION SECTION

R&S TYPE 2
(WARDROBE)



ELEVATION SECTION

R&S TYPE 3
(COUNTER WITH SINK)



SIDE ELEVATION

R&S TYPE 4
(SACRAMENTAL STORAGE UNIT)

NOTES

CASEWORK ITEMS SHOWN ON THIS SHEET SHALL BE OF PLASTIC LAMINATE MATERIAL AND CONSTRUCTION AS SPECIFIED. SEE ARCHITECTURAL DRAWINGS FOR ACTUAL ARRANGEMENT.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

TITLE: CHAPEL CASEWORK (R & S DETAILS)

DATE ISSUED: APRIL '80 — INTERIM COPY — REVISION

25D Veterans Administration STANDARD DETAIL



ELEVATION OF WALL

LEGEND OF MEDICAL GAS PIPED OUTLETS:

A — AIR

O — OXYGEN

V — VACUUM

Veterans Administration STANDARD DETAIL

26A

BED WALL OUTLETS - SECURITY ROOM (M.S.&N. NURSING UNIT)

TITLE

DATE ISSUED JULY '69

REVISION

NOTES

1. FURNITURE, LOCATIONS ARE AFFECTED BY LOCATIONS OF WINDOWS, COLUMNS, PIPE FURRING ETC. SEE ARCHITECTURAL PLANS.
2. SEE PLUMBING AND ELECTRICAL DRAWINGS & SPECIFICATIONS FOR FURTHER INFORMATION REGARDING ELECTRICAL AND PLUMBING WORK.
3. NIGHT LIGHT SHALL BE 18" ABOVE FLOOR AND LOCATED ON WALL OPPOSITE ROOM DOOR. SEE ELECTRICAL DRAWINGS.



ELEVATION OF WALL

Veterans Administration STANDARD DETAIL

26D

BED WALL OUTLETS- SINGLE SECURITY BED ROOM, PSYCHIATRIC (GENERAL) NURSING UNIT

TITLE

DATE ISSUED JULY '69

REVISION

NOTES

1. FURNITURE, LOCATIONS ARE AFFECTED BY LOCATIONS OF WINDOWS, COLUMNS, PIPE FURRING ETC. SEE ARCHITECTURAL PLANS.
2. SEE PLUMBING AND ELECTRICAL DRAWINGS & SPECIFICATIONS FOR FURTHER INFORMATION REGARDING ELECTRICAL AND PLUMBING WORK.
3. NIGHT LIGHT SHALL BE 18" ABOVE FLOOR AND LOCATED ON WALL OPPOSITE ROOM DOOR. SEE ELECTRICAL DRAWINGS.



ELEVATION OF WALL

Veterans Administration STANDARD DETAIL

266

BED WALL OUTLETS- SERVING A SINGLE BED- PSYCHIATRIC (GENERAL) NURSING UNIT

TITLE

DATE ISSUED MAR. '72

REVISION

NOTES

1. FURNITURE, LOCATIONS ARE AFFECTED BY LOCATIONS OF WINDOWS, COLUMNS, PIPE FURRING ETC. SEE ARCHITECTURAL PLANS.
2. SEE PLUMBING AND ELECTRICAL DRAWINGS & SPECIFICATIONS FOR FURTHER INFORMATION REGARDING ELECTRICAL AND PLUMBING WORK.
3. NIGHT LIGHT SHALL BE 18" ABOVE FLOOR AND LOCATED ON WALL OPPOSITE ROOM DOOR. SEE ELECTRICAL DRAWINGS.



ELEVATION OF WALL

Veterans Administration STANDARD DETAIL

26H

BED WALL OUTLETS SERVING TWO BEDS- PSYCHIATRIC (GENERAL) NURSING UNIT

TITLE

DATE ISSUED MAR. '78

REVISION

NOTES

1. FURNITURE, LOCATIONS ARE AFFECTED BY LOCATIONS OF WINDOWS, COLUMNS, PIPE FURRING ETC. SEE ARCHITECTURAL PLANS.
2. SEE PLUMBING AND ELECTRICAL DRAWINGS & SPECIFICATIONS FOR FURTHER INFORMATION REGARDING ELECTRICAL AND PLUMBING WORK.
3. NIGHT LIGHT SHALL BE 18" ABOVE FLOOR AND LOCATED ON WALL OPPOSITE ROOM DOOR. SEE ELECTRICAL DRAWINGS.

PLAN

ELEVATION

SECTION 1

SECTION 2

NOTES

1. Details to be modified to reflect finishes, partition types & other conditions peculiar to each project.

TYPICAL COMMUNICATION CENTER COUNTER PLANS

COMMUNICATION CENTER COUNTER

for all Nursing Unit types and the Emergency and Evaluation Area of Ambulatory Care.

TITLE

DATE ISSUED Jan. 81 REVISION May 87

27

Veterans Administration STANDARD DETAIL



TYPICAL PLAN

NOTE:

1. GRATINGS TO BE REMOVABLE UNLESS OTHERWISE SHOWN OR NOTED.
2. SEE PLANS FOR LOCATIONS OF HINGED OR FIXED UNITS OF GRATINGS.
3. PROVIDE HINGES AND LOCKS AS SPECIFIED FOR HINGED UNITS.
4. EXCEPT WHERE GRATINGS ARE NOTED ON PLANS AS HINGED OR FIXED THEY ARE TO BE PROVIDED WITH LUGS AND LOCKS AS SPECIFIED.
5. SEE ARCHITECTURAL AND/OR STRUCTURAL PLANS FOR SIZE AND LOCATION OF AREAS.
6. SEE STRUCTURAL DRAWINGS FOR THICKNESS OF CONCRETE AREA WALLS AND FOR REINFORCING OF SAME.
7. OTHER DESIGNS OF GRATING MAY BE USED, SEE SPECIFICATIONS.

AREA GRATING TYPE "A"

28

PLAN

ELEVATION OF SCREEN DOOR

SECTION A-A
(HEAD AND SILL SIMILAR)

SECTION A-A
WHERE EXIT OCCURS
ABOVE GRADE

NOTES

SEE ARCHITECTURAL AND/OR STRUCTURAL DRAWINGS FOR LOCATION OF THESE AREAS. OTHER GRATING DESIGNS MAY BE USED. SEE SPECIFICATIONS. SIZE OF AREAS FOR EMERGENCY EXITS TO BE AS SHOWN ABOVE UNLESS OTHERWISE SHOWN ON ARCHITECTURAL AND/OR STRUCTURAL DRAWINGS. ALL METAL OF DOOR AND FRAME TO BE GALVANIZED, METAL OF INSECT SCREEN TO BE AS SPEC'D, SEE STANDARD DETAIL 28 FOR OTHER SECTIONS & NOTES APPLICABLE TO THIS DWG.

AREA GRATING TYPE "C" (EMERGENCY EXIT FROM PIPE BASEMENT

TITLE

DATE ISSUED APRIL '80 | INTERIM COPY REVISION

28 4

Veterans Administration STANDARD DETAIL



















NOTES: (CONT.)
(SHOWN IN SECTION "X-X") SHALL BE REMOVABLE.
7. REMOVABLE MEMBERS SHALL BE SECURED TO CLIP ANGLES WITH BOLTS.
8. SEE ARCHITECTURAL AND/OR STRUCTURAL PLANS FOR SIZE 8, LOCATION OF AREAS.
9. SEE STRUCTURAL DWGS. FOR THICKNESS OF CONCRETE AREA WALLS AND FOR REINFORCEMENT OF SAME.
10. WHERE FACE BRICK OCCURS, EXPANSION BOLTS SHALL BE A MINIMUM OF 5" LONG.

NOTES
1. SEE SHEET NO. 28 FOR SEC. "C" & LOCK "D".
2. GRATINGS SHALL BE REMOVABLE UNLESS OTHERWISE SHOWN OR NOTED.
3. SEE PLANS FOR LOCATIONS OF HINGED OR FIXED UNITS OF GRATINGS.
4. PROVIDE HINGES AND LOCKS AS SPECIFIED FOR HINGED UNITS.
5. PROVIDE LUGS AND LOCKS AS SPECIFIED FOR REMOVABLE UNITS.
6. WHERE MULTIPLE GRATINGS ARE NOTED OR PLANS TO BE REMOVABLE, ALL STRUCTURAL MEMBERS (CONT.)

AREA GRATING
TYPES "B & D"

TITLE

DATE ISSUED APRIL '60 | INTERIM COPY
REVISION

28B

Veterans Administration STANDARD DETAIL



NOTE:
SEE STRUCTURAL DRAWINGS FOR VARIATIONS FROM THIS DIMENSION WHEN SECONDARY SLAB IS OMITTED AT TOP OF HOISTWAY.

FRONT & REAR ENTRANCES
(ALSO APPLIES TO PLANS "B" & "C")
AVOID REAR ENTRANCES IF POSSIBLE

(5'-8" x 6'-8" CAR)

(5'-8" x 9'-1½" CAR)

PLAN "A"



PLAN "B"
(5'-8" x 8'-8" CAR)



PLAN "C"
(5'-8" x 8'-8" CAR)



SECTION "A-A"

NOTES

1. SEE ARCHITECTURAL DRAWINGS FOR WALL TYPE & FINISH.
2. SEE STRUCTURAL DRAWINGS FOR ACTUAL SIZE & LOCATION OF COLUMNS, BEAMS & SLABS.
3. SEE SHEET 29A FOR ELEVATIONS & DETAILS OF TWO SPEED SLIDING DOORS.

ELEVATORS, PASSENGER
(TWO SPEED SLIDING DOORS)

TITLE

DATE ISSUED APRIL '80 | INTERIM COPY | REVISION

29

Veterans Administration STANDARD DETAIL



HEAD



ELEVATION OF DOORS



SECTION "A-A"



SILL



PLAN

NOTES

HEAD AND JAMBS OF FINISHED FRAME SHALL BE SECURED TOGETHER WITH CONTINUCUS WELD.

ALL METAL BASES AND FINISHES OF FRAME AND DOORS AS SPECIFIED.

FOR TOP FLOOR DUST COVER AND BOTTOM FLOOR TOE GUARD, SEE STANDARD DETAIL Nº. 298.

DOORS MAY BE RIGHT OR LEFT HAND - ARCHITECT TO SPECIFY.

ELEVATORS, PASSENGER-ENTRANCE DETAILS

(TWO SPEED SLIDING DOORS)

TITLE

INTERIM COPY

DATE ISSUED APRIL '80 | REVISION

Veterans Administration STANDARD DETAIL 529



PLAN "D"
(6'-8" x 8'-8" CAR)



PLAN "E"
(6'-8" x 9'-1 1/2" CAR WITH FRONT AND REAR ENTRANCES)

NOTE: AVOID REAR ENTRANCE WHERE POSSIBLE.

PLANS



TOP FLOOR-DUST COVER @ HEAD
SCALE: 1/2" = 1'-0"



BOTTOM FL.-TOE GUARD @ SILL



TOP & BOTTOM DEFLECTOR FOR PROJECTING BEAM IN HOISTWAY



SECTION "A-A"

NOTES
1. SEE ARCH. DWGS FOR WALL TYPE FIN.
2. SEE STRUCT. DWGS. FOR ACTUAL SIZE & LOCATION OF COLUMNS, BEAMS & SLABS.
3. SEE SHT. NO. 29C FOR ELEV. & DETS. OF HORIZ. SLIDING CENTER OPENING DOORS.
4. UNASSOCIATED WATER PIPES, DUCT WORK, EQUIP., ETC. ARE NOT PERMITTED IN MACH. RMS. OR HOISTWAYS
5. CONC. MACH. RM. FL.(S) NOT TO BE POURED UNTIL MACHINES ARE ON MACHINE BEAMS.
6. MACH. RM.- APPROX. 225 SQ. FT. PER MACHINE.
7. TOP OF MACH. BEAMS SHALL BE FLUSH W/OR BELOW MACHINE RM. FL. SLAB.

ELEVATORS, SERVICE
(HORIZONTAL SLIDING CENTER OPENING DOORS)

TITLE

INTERIM COPY

DATE ISSUED APRIL '80

REVISION

B 29

Veterans Administration STANDARD DETAIL



NOTES

HEAD AND JAMBS OF FINISHED FRAME SHALL BE SECURED TOGETHER WITH CONTINUOUS WELD.

ALL METAL BASES AND FINISHES OF FRAME AND DOORS AS SPECIFIED.

ELEVATORS, SERVICE & PASSENGER ENTRANCE DETAILS

(HORIZONTAL SLIDING CENTER OPENING DOORS)

TITLE

INTERIM COPY

DATE ISSUED APRIL '80 | REVISION

29 C

Veterans Administration STANDARD DETAIL



HEAD
(TOP ENTRANCE)



HEAD
(BOTTOM ENTRANCE)



TYPICAL ELEVATION



TYPICAL SILL



TYPICAL JAMB



JAMB AT "A-A"

NOTES

1. PROVIDE 9" ℄ FRAME & 9" x 4" x 1/2" SILL ANGLE WHERE ELEVATOR ENTRANCE OCCURS IN 8" BRICK WALL.
2. CAULK AROUND EDGE OF ℄ FRAME WHERE S.F.T.U. FINISH OR EXPOSED MASONRY OCCURS.
3. PASS TYPE FREIGHT ELEVATOR DOORS TO BE USED WHERE STORY HEIGHT WILL NOT PERMIT CLEARANCE BETWEEN DOORS OF TOP AND BOTTOM ENTRANCES WHEN ONE IS OPEN.

VERTICAL SLIDING BI-PARTING PASS-TYPE FREIGHT ELEVATOR DOORS

TITLE

DATE ISSUED DEC. '81 | REVISION

29D

Veterans Administration STANDARD DETAIL

VARIABLE CAR DIMENSIONS		
	4000LB. CAP.	5000LB. CAP.
A	7'-4"	8'-4"
B	5'-8"	6'-8"
C	5'-4"	6'-4"
D	2'-5"	3'-5"



PLAN OF ELEVATOR AT BOTTOM FLOOR



DETAIL OF WELL CASING AND PLUNGER ASSEMBLY



SECTION "A-A"

NOTES

1. SEE SPECIFICATIONS SECTION 9XD FOR CORROSION PREVENTIVE TREATMENT OF CASING AND HYDRAULIC CYLINDER.
2. UNASSOCIATED WATER PIPES, DUCTWORK, EQUIPMENT, ETC. ARE NOT PERMITTED IN MACHINE ROOM OR HOISTWAYS.
3. DOORS MAY BE DESIGNED TO SLIDE RIGHT OR LEFT. ARCHITECT TO INDICATE.

ELEVATORS, HYDRAULIC

PLAN & SECTION

INTERIM COPY

DATE ISSUED	REVISION
APRIL '80	

TITLE

Veterans Administration STANDARD DETAIL

29 E

SCHEDULE OF APPROXIMATE OVERHEAD HEIGHTS AND PIT DEPTHS FOR 4000# CAPACITY PASSENGER ELEVATORS

OVERHEAD MACHINES

SPEEDS FT. PER MIN.	TYPE OF MACHINE	DISTANCE FROM TOP LANDING TO FIN. MACHINE ROOM FLOOR OR PLATFORM		DISTANCE FROM TOP OF FINISHED MACHINE FLOOR TO UNDERSIDE OF SECONDARY SLAB.	PITS
		WITHOUT SECONDARY SLAB	WITH SECONDARY SLAB		
100	GEARED	16'-6"			5'-6"
150	"	16'-6"			5'-6"
200	"	16'-6"			5'-6"
250	"	18'-0"			7'-0"
300	"	18'-0"			7'-0"
350	"	18'-6"			7'-0"
400	GEARLESS		24'-3"	6'-3"	8'-8"
450	"		24'-3"	6'-3"	8'-8"
500	"		25'-3"	6'-3"	10'-0"
600	"		27'-0"	6'-3"	12'-6"
700	"		28'-0"	6'-3"	12'-6"

CLEAR MACHINE ROOM WITHOUT TROLLEY BEAMS 7'-6" MIN.
CLEAR MACHINE ROOM WITH TROLLEY BEAMS 10'-0" MIN.

Veterans Administration STANDARD DETAIL 29F

ELEVATOR HOISTWAYS

(PASSENGER)

VERTICAL DIMENSIONS

TITLE

DATE ISSUED JUNE '80

REVISION

NOTES

1. ELEVATOR ENGINEER SHOULD BE CONSULTED RELATIVE TO CLEARANCES REQUIRED FOR SPECIFIC PROJECTS.

SCHEDULE OF APPROXIMATE OVERHEAD HEIGHTS AND PIT DEPTHS FOR 5000# CAPACITY SERVICE ELEVATORS

OVERHEAD MACHINES

SPEEDS FT. PER MIN.	TYPE OF MACHINE	DISTANCE FROM TOP LANDING TO FIN. MACHINE ROOM FLOOR OR PLATFORM		DISTANCE FROM TOP OF FINISHED MACHINE FLOOR TO UNDERSIDE OF SECONDARY SLAB.	PITS
		WITHOUT SECONDARY SLAB	WITH SECONDARY SLAB		
100	GEARED	16'-6"			5'-6"
150	"	16'-6"			5'-6"
200	"	18'-6"			5'-6"
250	"	18'-0"			7'-0"
300	"	18'-0"			7'-0"
350	"	18'-6"			7'-0"
400	GEARLESS		24'-3"	5'-3"	8'-8"
450	"		24'-3"	6'-3"	8'-8"
500	"		25'-3"	6'-3"	10'-0"
600	"		27'-0"	6'-3"	12'-6"
700	"		28'-0"	6'-3"	12'-6"

CLEAR MACHINE ROOM WITHOUT TROLLEY BEAMS 7'-6" MIN.
CLEAR MACHINE ROOM WITH TROLLEY BEAMS 10'-0" MIN.

29G
Veterans Administration STANDARD DETAIL

ELEVATOR HOISTWAYS

(SERVICE)

VERTICAL DIMENSIONS

TITLE

DATE ISSUED

REVISION

NOTES

1. ELEVATOR ENGINEER SHOULD BE CONSULTED RELATIVE TO CLEARANCES REQUIRED FOR SPECIFIC PROJECTS

NOTE:
SEE STRUCTURAL DRAWING FOR VARIATIONS FROM THIS DIMENSION WHEN SECONDARY SLAB IS OMITTED AT TOP OF HOISTWAY.



PLAN "F"
(8'-0" x 6'-2" PLATFORM)



TOP & BOTTOM DEFLECTOR FOR PROJECTING BEAM IN HOISTWAY



SECTION "A-A"

NOTES
1. SEE ARCH. DWGS. FOR WALL TYPE & FIN. LOCATION OF COL., BEAMS & SLABS.
2. SEE STRUC. DWGS. FOR ACTUAL SIZE & 3. SEE SHEET NO. 29C FOR ELEVATION & DETAILS OF HORIZONTAL SLIDING CENTER OPENING DRS.
4. UNASSOCIATED WATER PIPES, DUCTWORK, EQUIP., ARE NOT PERMITTED IN MACHINE RMS. OR HOISTWAYS.
5. CONCRETE FL. (S) NOT TO BE POURED UNTIL MACHINES ARE IN PLACE.
6. MACHINE RM - APPROX. 225 SQ. FT. PER MACHINE.
7. MACHINE BEAMS SHALL BE FLUSH OR BELOW MACHINE RM FL. SLAB.

ELEVATORS, PASSENGER
HORIZONTAL SLIDING CENTER OPENING DOORS

TITLE

INTERIM COPY

DATE ISSUED APRIL '50 | REVISION

29H

Veterans Administration STANDARD DETAIL

NOTES

1. HEAD AND JAMBS OF FINISHED FRAME SHALL BE SECURED TOGETHER WITH CONTINOUS WELD.

2. ALL METAL GAGES AND FINISHES OF FRAME AND DOORS AS SPECIFIED.

ELEVATORS, SERVICE & PASSENGER

ENTRANCE DETAILS

(WITH DRYWALL SHAFT)

(HORIZONTAL SLIDING CENTER OPENING DOORS)

TITLE

DATE ISSUED APRIL '80 | INTERIM COPY | REVISION

29
J

Veterans Administration STANDARD DETAIL



EXPANSION JOINT AT FLOOR



EXPANSION JOINT IN GYM. AT FLOOR & WALL



EXPANSION JOINT AT FLOOR & WALL



EXPANSION JOINT IN GYM. FLOOR



EXPANSION JOINT AT WALL AND CEILING



EXPANSION JOINT AT WALL OR CEILING

NOTES

1. SEE SHEET NO. 31 FOR ADDITIONAL EXPANSION JOINT DETAILS. (SEISMIC)
2. *USE BRONZE STD. MANUFACTURERS EXPANSION JOINT COVER PLATES AT ALL FIRE RATED PARTITIONS.
3. EXPANSION JOINTS IN FIRE RATED PARTITIONS SHALL BE PACKED WITH MINERAL WOOL INSULATION.

TITLE: EXPANSION JOINT COVER PLATES

DATE ISSUED APRIL 80 | INTERIM COPY | REVISION

30

Veterans Administration STANDARD DETAIL



NOTE: MAXIMUM SPACING OF VERTICAL MEMBERS SHALL BE 6'-0"

TYPICAL ELEVATIONS OF REMOVABLE PIPE RAILINGS



METAL POST INSERTS FOR RAILINGS



FIXED POST
PIPE RAILING POST INSERT
IN CONCRETE (EXTERIOR)



REMOVABLE PIPE RAILING DETAILS WITH POST INSERTS IN CONCRETE



FIXED POST
PIPE RAILING POST INSERT
IN BRICK OR FLAGSTONE



PIPE RAILING POST IN STONE

NOTES

1. WHERE BEAM OR REINFORCING RODS OCCUR DIRECTLY UNDER VERT. MEMBERS OF PIPE RAILINGS, OMIT PIPE SLEEVE INSERTS AND PROVIDE FL. FLANGES WELDING OR THREADED TO POSTS OR VERT. MEMBERS AND EXPANSION BOLTED TO CONCRETE.
2. HANDRAILS SHALL BE SO CONSTRUCTED AS TO WITHSTAND A FORCE OF 200 LBS. APPLIED DOWNWARD OR HORIZONTAL AT ANY POINT.
3. RAILINGS ARE 1 1/4" STANDARD PIPE AND SLEEVES ARE APPROXIMATELY 1" LARGER.

TITLE: RAILING DETAILS

INTERIM COPY

DATE ISSUED: [illegible] '80

REVISIONS

32

Veterans Administration STANDARD DETAIL



LADDER TO ELEVATOR MACHINE PLATFORM



TYPICAL LADDER DETAILS

NOTE: FOR MAXIMUM LENGTH OF LADDER SEE OSHA REQUIREMENTS.



TYPICAL LADDER IN ELEVATOR PIT



PLAN



TYPICAL SECTION OF LADDER ADJACENT TO DIVISION BEAM



SECTION OF LADDER WHEN INTERRUPTED BY DIVISION BEAM

ELEVATOR PIT LADDER AT DIVISION BEAM



DETAIL "A"



DETAIL "A" IN SOLID MASONRY WALL



SECTION

TYPICAL ROOF LADDER

NOTES

LADDER DETAILS

TITLE

DATE ISSUED Sept. '79 REVISION

33

Veterans Administration STANDARD DETAIL



ACCESS DOOR



ELEVATION

NOTES TO ARCHITECT

1. Reverse ladder where required. Ladder & bar grip shall be placed at lock side of door.
2. Wire mesh access doors shall be used when required between Service Room & Pipe Basement.
3. Size of door shall be noted on Arch. plans.
4. Provide metal ladder where pipe basement floor is over 3'-6" above service room floor.
5. For max. length of ladder, see OSHA requirements.
6. See Std. Det. 33 for additional ladder details.

ACCESS DOOR (WIRE MESH) & LADDER

TITLE

DATE ISSUED Oct '78 | REVISION Jan '79

34

Veterans Administration STANDARD DETAIL



SECTION "A - A"



SECTION "B - B"



DETAIL OF LIFT HANDLE



HALF PLAN

NOTE:
FOR REMOVABLE PIPE RAILING & POSTS (SEE STD. DETAIL N° 32)



PLAN



SECTION

NOTE:
REFER TO ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR LOCATION AND SIZE OF OPENINGS.

NOTES

TRAP DOORS IN ELEVATOR PENTHOUSE FLOOR

TITLE

DATE ISSUED Sept. '79 REVISION 5/22/80

35

Veterans Administration STANDARD DETAIL



SECTION THRU SUPPORT SYSTEM



C



D



A



B

NOTE FOR ARCHITECT

DETAILS A, B, C & D SHOW ANCHORAGE SUPPORT INTO VARIOUS TYPES OF SLAB CONDITIONS. ACTUAL SUPPORT MUST BE DESIGNED TO SUIT THE PARTICULAR SITUATION.

NOTES

- ... AND HANGERS SHALL BE ARRANGED ... ON ARCHITECTURAL DRAWINGS AND ... APPROV... ROM FACE OF ... TERMINATE ...
- ... PARTITIONS, EXCEPT FOR MEMBERS FLUSH WITH CEILING.
- ... MEMBER SHOWN ON DRAWING ... NUMBERS USED ... ARE UNISTRUT CATALOG ... AS A CONVENIENCE FOR IDENTIFYING DESIRED SHAPES AND THICKNESS OF MEMBERS.

SUPPORT SYSTEM FOR CEILING MOUNTED X-RAY EQUIPMENT

TITLE

DATE ISSUED APRIL '80 REVISION JUN. '82

36

Veterans Administration STANDARD DETAIL



SECTION "A"

(AT A. T CEIL'G)



SECTION "A"

(AT PLASTER CEIL'G.)



DETAIL



PLAN

SCALE: 1/2" = 1'-0"

NOTES

1. WHENEVER POSSIBLE, SECURE TRACK DIRECTLY TO EXPOSED MAIN TEES.
2. WHENEVER NOTE #1 IS NOT POSSIBLE, SECURE CURTAIN TRACK TO L SPANNING BETWEEN MAIN TEES.

PLAN OF I. V. TRACK & CEILING ANCHORAGE

(CUBICAL CURTAIN TRACK SIMILAR)

TITLE

DATE ISSUED APRIL'80 | INTERIM COPY REVISION 3/4/80

364

Veterans Administration STANDARD DETAIL



TYPICAL PARTIAL PLATFORM PLAN



PARTIAL PLATFORM PLAN WHERE ADJ. RAMP OCCURS



SECTION THRU CANOPY & PLATFORM



DETAIL "A" BUMPER DETAIL

NOTE: SEE STANDARD DETAIL 37A FOR ENCLOSED LOADING DOCKS FOR USE IN COLD CLIMATES.

NOTES

1. ADJ. RAMP LOCATION TO BE DETERMINED FOR EACH PROJECT.
2. LOADING DOCK SHALL BE A MINIMUM OF 11'-0" DEEP WHERE ADJ. RAMPS ARE REQUIRED.
3. SEE VETERANS ADMINISTRATION CONSTRUCTION STANDARD 1-5, AND [illegible] DETAIL 7D.

TITLE: LOADING PLATFORM AND CANOPY

DATE ISSUED JAN. '61 | REVISION JUNE '62

37 Veterans Administration STANDARD DETAIL

SECTION A-A

ELEVATION

NOTES:

1. DOOR SIZE: 8'-0" WIDE x 9'-0" HIGH.
2. DOCK LEVELER/POWER RAMP & DIMENSIONS TO BE INSTALLED AS PER MANUFACTURER'S REQUIREMENTS.
3. WHEN USING MORE THAN ONE LOADING DOCK DOOR, SPACE DOORS AS REQUIRED FOR SPACE FUNCTION.
4. WHEN USING MORE THAN ONE LOADING DOCK DOOR, PROVIDE ONLY ONE DOCK LEVELER.
5. STRUCTURAL SUPPORT AND ANCHORAGE SHALL BE AS PER MANUFACTURER'S REQUIREMENTS.
6. USE WHERE WINTER DESIGN TEMP. IS BELOW 10° F AS GIVEN IN THE 97½% COLUMN OF TABLE I, ASHRAE HANDBOOK OF FUNDAMENTALS.

PLAN

NOTES

1. SEE STANDARD DETAIL 7D FOR ROLL-UP DOOR DETAILS

WAREHOUSE RECEIVING DOOR FOR END-LOAD

TITLE

DATE ISSUED JAN. '81 | REVISION JUN. '82

37A Veterans Administration STANDARD DETAIL



Veterans Administration STANDARD DETAIL

38

LETTER BOX & MAIL CHUTE

TITLE

DATE ISSUED Mar. '78

REVISION

NOTES

1. LETTER BOX AND MAIL CHUTE SHALL BE OF ALUMINUM AS SPECIFIED.
2. LOCATE LETTER BOX AT THE BASE OF MAIL CHUTE IN THE ELEVATOR LOBBY ON THE SAME LEVEL AS THE LOADING DOCK. THIS LOCATION IS SUBJECT TO THE APPROVAL OF THE POSTMASTER.
3. ALL MAIL CHUTE EQUIPMENT SHALL CONFORM TO THE LATEST RULES, REGULATIONS & SPECIFICATIONS OF THE POSTAL SERVICE.



EDGE STRIP

AT EXPOSED EDGE OF RESILIENT FLOORING



METAL FLOOR STRIP

BETWEEN WOOD AND OTHER FLOORING



CARPET MOULDING STRIP

BETWEEN TILE FINISH AND CARPET FLOOR



RESILIENT REDUCER STRIP

BETWEEN TILE FINISH AND RESILIENT FINISH ON EXIST. CONCRETE FLOORS OR ON NEW CONC. FLOORS WITHOUT TOPPING



METAL DIVIDER STRIP

IN CONCRETE TOPPING WITH DIFFERENT FINISH ON EACH SIDE



CARPET MOULDING STRIP

BETWEEN RESILIENT FLOORING AND CARPET FLOOR

NOTES

FLOOR STRIPS

TITLE

DATE ISSUED JULY '77 | REVISION

39

Veterans Administration STANDARD DETAIL

NOTES:-

1. INVERT ELEVATION OF DRAIN PIPE SHALL NOT BE HIGHER THAN TOP OF LOWEST FLOOR ELEVATION.

2. DRAIN PIPE SHALL SLOPE UNIFORMLY BETWEEN ELEVATIONS SHOWN ON FOUNDATION DRAINAGE PLANS.

3. WHERE FOUNDATION DRAIN IS WITHIN 24" OF FINISHED GRADE, ONE HALF OF FILL SHALL BE MADE WITH CRUSHED STONE.

4. INVERT ELEVATION OF DRAIN PIPE SHALL NOT BE LOWER THAN BOTTOM OF FOOTING.



FOUNDATION DRAIN DETAIL

40

JUNE 79

ARCHITECTURAL STANDARD DETAIL



41

Veterans Administration STANDARD DETAIL

INTERVIEW BOOTH

TITLE

DATE ISSUED JAN. '79

REVISION

NOTES

1. ADDITIONAL BOOTHS MAY BE ADDED, AS REQ'D. CHECK SPACE SHEETS. (MIN. OF 2, MAX. OF 6)





Veterans Administration STANDARD DETAIL

42

WHEEL CHAIR DIMENSIONS

TITLE

DATE ISSUED JULY '69

REVISION

NOTES



SIGN TYPE 1



SIGN TYPE 2





NOTES

BUILDING SIGN
(EXTERIOR FACE)

TITLE

DATE ISSUED MAY '80 REVISION 12-1180

43A

Veterans Administration
STANDARDS

FUNCTION
TO IDENTIFY ALL ROOMS, D1 - ROOM NUMBERS

MODULE SIZE
D1 - 3"X9"

COPY SIZE
D1 - 1 1/4" OR 1 1/2"

SPECIAL DATA
MODULE D1 SHALL HAVE TACTILE CHARACTERS RAISED 1/32" MIN, 1/8" MAX AND ACID WELD TO BACK PANEL.



DIMENSIONAL ROOM NUMBER

FUNCTION
GRAPHIC DIRECTION OR IDENTIFICATION.

MODULE SIZE
9"X9"
INCLUDING FRAME

COPY SIZE
3/4" MINIMUM

SPECIAL DATA
SYMBOLS MUST BE ACCOMPANIED VERBAGE. MUST BE PHOTOGRAPHICALLY REPRODUCED. HAND CUT IMAGES UNACCEPTABLE. GRAPHIC SYMBOLS USED IN SQUARE FORMAT SHALL BE CENTERED ON FOUR SIDES.



GRAPHIC SYMBOLS



FIRE SAFETY SIGNS

FUNCTION
PROVIDE EMERGENCY, FIRE EVACUATION INFORMATION.

MODULE SIZE
V3 - 9" X 9"
V4 - 9" X 9"
V5 - 9" X 9"

SPECIAL DATA
V3 - SHALL BE DISPLAYED AT EVERY ELEVATOR CALL BUTTON.
V4 - MUST BE POSTED ON ANY DOOR THAT COULD BE FASELY CONSTRUED AS AN EXIT.
V5 - TO BE DISPLAYED ON EVERY FIRE DOOR NOT AUTOMATICALLY OPERATED.

GENERAL NOTE
SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION

NOTES
1. FOR COPY TYPES SIZE, SPACING AND COLOR SEE SPECIFICATIONS.

TITLE
INTERIOR SIGNAGE

DATE ISSUED JAN. '81 | REVISION 4/3/86

43B
Veterans Administration STANDARD DETAIL



ELEVATION



SECTION

FRAME INSTALLATION



ANCHORAGE DETAIL

RIGHT ANGLE SIGN



GRAPHIC SYMBOL ROOM NUMBER

INSTALLATION PLACEMENT

NOTES

1. FOR COPY TYPES SIZE & SPACING SEE SPECIFICATIONS.
2. FOR SIGNAGE COLOR SPECIFICATIONS.

INTERIOR SIGNAGE

TITLE

DATE ISSUED JAN. '81

REVISION

43C

Veterans Administration STANDARD DETAIL





SECTION ON ℄

ALL LETTERING TO BE PAINTED BLACK WITH EXCEPTION OF PROJECT TITLE WHICH IS TO BE BLUE

NOTE:
ANY SEAM IN METAL TO BE FLAT SEAM-SEAMS TO BE HORIZONTAL AND OCCUR BETWEEN LINES OF LETTERING.

NOTES

SIGN SHALL BE USED FOR PROJECTS OVER $250,000.00.
SEE STD. DETAIL NO. 44A FOR LOGO DETAILS.

CONSTRUCTION SIGN

(FOR PROJECTS WITH WORKING DRAWINGS BY A/E)

TITLE

DATE ISSUED APRIL 80 REVISION 10/3/83

44

Veterans Administration STANDARD DETAIL



V.A LOGO

NOT SHOWN TO SCALE

NOTES

V. A. LOGO

TITLE

DATE ISSUED APRIL 80 REVISION 3/82

44A

Veterans Administration STANDARD DETAIL



NOTES

1 BORDER MEMBERS TO BE PAINTED BLACK.
2 BACKGROUND TO BE PAINTED WHITE.
3 ALL LETTERING TO BE PAINTED BLACK WITH EXCEPTION OF PROJECT TITLE WHICH IS TO BE BLUE.

CONSTRUCTION SIGN

(FOR PROJECTS WITH WORKING DRAWINGS BY V.A.)

TITLE

DATE ISSUED 10/3/83 | REVISION

44B

Veterans Administration STANDARD DETAIL

ATTACHMENT TO SECTION 01, GENERAL REQUIREMENTS

Veterans Administration STANDARD DETAIL 45

SAFETY SIGN

TITLE

DATE ISSUED JAN. '76

REVISION

NOTES

BOARD TO BE MADE OF 3/4" EXTERIOR PLYWOOD. BOARD TO BE PAINTED WITH ONE PRIME COAT AND TWO COATS OF WHITE ENAMEL LETTERING TO BE IN BLACK ENAMEL EXCEPT AS NOTED. THREE (S) SETS OF REMOVABLE NUMBERALS PAINTED ON 1/8" TEMPERED PRESSED HARDBOARD SHALL BE PROVIDED. SIGN TO BE LOCATED ON OR NEAR THE PRIME CONTRACTOR'S OFFICE.



Veterans Administration STANDARD DETAIL

45A

SYMBOL OF ACCESSIBILITY TO THE HANDICAPPED

TITLE

DATE ISSUED JAN.'76

REVISION

NOTES

THE ACCESSIBILITY SYMBOL SIGN IS TO HAVE WHITE (REFLECTORIZED) LEGEND ON A BLUE BACKGROUND. THE SYMBOL SIGN SHALL BE USED TO IDENTIFY FACILITIES AND AREAS THAT ARE FULLY ACCESSIBLE TO AND USEABLE BY ALL HANDICAPPED INDIVIDUALS. SEE VA CONSTRUCTION STANDARD (CD-28, PARAGRAPH 5J).



PLAN OF THERAPEUTIC POOL



(A) SECTION THRU THERAPEUTIC POOL



(B) SECTION THRU RAMP

(C) DET. AT GUTTER

(D) DETAIL AT TRANSFER CURB

Veterans Administration STANDARD DETAIL

47

THERAPEUTIC POOLS
60'-0" L x 28'-0" W AND
60'-0" L x 35'-0" W

TITLE

DATE ISSUED Sept. '79 | REVISION 10/3/83 | RJC

NOTES

POOL WALLS WITH LIGHTS MUST BE SUFFICIENTLY THICK TO ACCOMODATE 9" TO 10" DEEP RECESSED UNDERWATER LIGHTS



47A

Veterans Administration STANDARD DETAIL

THERAPEUTIC POOL
40'.0" L x 33'.0" W

TITLE

DATE ISSUED Sept. '79 | REVISION

NOTES



NOTE: CONSULT O/C IF ALLOWABLE SOIL BEARING PRESSURE IS LESS THAN 3,000 POUNDS PER SQUARE FOOT.

FLAGPOLE & FOOTING DIMENSIONS

EXPOSED HEIGHT IN FEET	DIA. OF BALL	DIA. OF POLE AT TOP	DIA. OF POLE AT BUTT	A	B	C	D	E	F	G	H
	DIMENSIONS IN INCHES										
40	8	3 1/2	7 5/8	12	48	9	36	45	16	4	18
45	8	3 1/2	8 5/8	12	54	9	36	45	16	4	18
50	10	3 1/2	9 5/8	14	60	10	42	48	18	4 1/2	20
60	10	4	10 3/4	14	72	12	42	48	18	4 1/2	24
65	12	4	11 3/4	16	78	12	42	48	20	5	24
70	12	4	12	18	84	12	42	60	22	6	24
75	14	4	12	18	90	12	42	60	22	6	24

ALL DIMENSIONS ARE MINIMUM

NOTES

1. Foundations shall be properly designed for flagpoles of lesser or greater height than those shown in schedule above.
2. VA Cemetery Service shall advise the Architect when halyards are to be installed within the pole.
3. For pole height limitations see VA Construction Standard CD-7.

TITLE: FLAGPOLE DETAILS

DATE ISSUED JUNE '78 | REVISION 3/11/82

79

Veterans Administration STANDARD DETAIL



SEAL SIZE "C"



SEAL SIZE "B"

SEAL SIZE "A"

ELEVATIONS
OF SEALS

NOTE :-
ANCHOR BOLTS SHALL EXTEND 2" MIN.
INTO SOLID MASONRY OR CONCRETE.
DRILL 1/2" HOLES IN MASONRY OR CONCRETE
AND FILL WITH EXPOXY BEFORE INSERTING
THREADED BOLTS, PROVIDE SPECIAL DETAIL
OF ANCHORAGE WHERE SEAL IS ATTACHED
TO OTHER MATERIAL.



1/2 F. S. DETAIL
OF FASTENING

Veterans Administration STANDARD DETAIL 50

SEALS, EXTERIOR

TITLE

DATE ISSUED MAR.'78 | REVISION 12/29/82 FC

NOTES

1. SEALS SHALL BE PLACED WHERE INDICATED ON DRAWINGS.
2. SEALS WILL BE FURNISHED BY THE VETERANS ADMINISTRATION AND INSTALLED BY THE CONTRACTOR.
3. SIZE SELECTED SHALL BE DETERMINED BY THE V.A.
4. MATERIAL SHALL BE CAST BRONZE.



ELEVATION OF PLAQUE



1/2 F.S. DETAIL OF FASTENING

Veterans Administration STANDARD DETAIL

50A

DEDICATION PLAQUES

TITLE

DATE ISSUED SEPT. '79

REVISION

NOTES

1. A PLAQUE SHALL BE LOCATED IN THE LOBBY OF THE BUILDING TO BE DEDICATED. IF THERE IS NO LOBBY OR THE LOBBY IS UNSUITALBE FOR MOUNTING A PLAQUE, THE PROJECT DIRECTOR SHALL INDICATE TO THE A/E A SUITABLE LOCATION FOR THE PLAQUE.
2. PLAQUE WILL BE FURNISHED BY THE VETERANS ADMINISTRATION AND INSTALLED BY THE CONTRACTOR.
3. MATERIAL WILL BE CAST BRONZE.



ELEVATION SECTION

BENCH TYPE 29A

NOTE: BENCH TYPE 29B SIMILAR TO TYPE 29A EXCEPT AS OTHERWISE NOTED.



ELEVATION

BENCH TYPE 29B



ELEVATION SECTION

BENCH TYPE 29

NOTE:
BENCH LEGS AT WALL SHALL BE CUT TO FIT COVE OF ROOM BASE.
BENCHES SHALL BE SECURED TO FLOOR AND WALL AS INDICATED WITH TOGGLE OR EXPANSION BOLTS.
SEE ARCHITECTURAL PLANS FOR LOCATION OF SINK WHERE REQUIRED IN BENCHES TYPES 29, 29B AND 30A.
PROVIDE GOOSE NECK FAUCET, SURFACE MOUNTED, FOR SINK IN BENCHES TYPES 29 AND 29B.
SEE ARCH. PLANS FOR ANY VARIATION IN LENGTH OR HEIGHT OF TYPE 29.

NOTES

BENCHES
TYPES 29, 29A & 29B

TITLE

DATE ISSUED DEC. '74 | REVISION 6/82

52

Veterans Administration STANDARD DETAIL



ELEVATION



SECTION "B-B" AT CARRIER



SECTION "E-E" - AT WALL



SECTION "A-A" AT LAVATORY



PLAN



PLAN SECTION - CARRIER

1 1/2" = 1'-0"



SECT. "B-B" AT FLOOR - CARRIER

PREFERRED LOCATION OF DUPLEX OUTLET IF SIDE WALL EXTENDS FAR ENOUGH.



1/2 F.S. DET. "C"

FRONT EDGE



1/2 F.S. DET. "D"

BACKSPLASH CAP

NOTES

VANITY, SINGLE W/C-TYPE S4

TITLE

DATE ISSUED JAN. '79

REVISION 6/17/94 KD

53

Veterans Administration STANDARD DETAIL







NOTES

SPOUT & WRIST BLADE OR SINGLE HANDLE FAUCETS MAY BE USED AT EACH LAV. AS DETERMINED FOR EACH PROJECT OR ON AN INDIVIDUAL BASIS.

SEE STD. DETS., 53 AND 53B FOR DETAILS NOT SHOWN ON THIS SHEET.

VANITY, MULTIPLE
WHEEL CHAIR - TYPE S-4M

TITLE

DATE ISSUED JAN. '79

REVISION 96 [illegible]

53A

Veterans Administration STANDARD DETAIL



53B

Veterans Administration STANDARD DETAIL

PAPER TOWEL DISPENSER
FOR MULTIPLE LAVATORIES @ W/C VANITIES

TITLE

DATE ISSUED Sept. '79 | REVISION 6/17/86

NOTES

1. USE FOR W/C VANITIES WITH 2 OR MORE BASINS UNLESS "WING WALLS" ARE PROVIDED TO ALLOW PAPER TOWEL DISPENSER & ELECTRICAL OUTLET ADJACENT TO EACH BASIN.





NOTES

1. FOR CARRIER SUPPORT DETAILS SEE PLAN SECTION & SECTION "B"B" ON STD. 53.
2. ALL EXPOSED SURFACES TO BE LAMINATED PLASTIC, CORNERS BEVELED.
3. CONTRACTOR SHALL SUPPLY SHOP DRAWINGS SHOWING LARGE SCALE DETAILS OF CABINET WORK, MATERIAL SIZES & JOINTING.

PREVENTIVE DENTISTRY PATIENT PARTICIPATION MODULE

TITLE

DATE ISSUED JAN. '79	REVISION

53C

Veterans Administration STANDARD DETAIL

best copy available

NOTES

1. FOR USE IN ALL PATIENT BEDROOM AND TOILET/BATHROOMS EXCEPT SCI, NURSING HOME CARE UNITS, OR WHERE NURSERYERS ARE PROVIDED.

VANITY, SINGLE
TYPE S5

53D

Veterans Administration STANDARD DETAIL

TITLE

DATE ISSUED 11-2-87

REVISION 6/11/86 PB



BOOK CASE - TYPE 24

54

Veterans Administration STANDARD DETAIL

BOOK CASE TYPE 24

TITLE

DATE ISSUED DEC. 74

REVISION

NOTES

NOTE TO CONTRACTOR: PROVIDE SHOP DRAWINGS FOR SECTIONS SHOWN (↓ ↓)

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66





F.S. DETAIL OF DESK TOP

DESK IN CREDIT UNION OFFICE

DEC-'74

55

VA ARCHITECTURAL STANDARD DETAIL



NOTE: PHONES & CABINETS SHALL BE FURNISHED AND INSTALLED BY TELEPHONE COMPANY.

PUBLIC TELEPHONE

APRIL '80 56



SECTION-THRU
FIRE APPARATUS CABINET



ELEVATIONS

Veterans Administration STANDARD DETAIL 56A

FIRE APPARATUS CAB., VALVE CABINET, & EXTINGUISHER CABINET

TITLE

DATE ISSUED SEPT. '79 | REVISION 7/21/80

NOTES

1. TYPE OF CABINET TO BE DETERMINED BY ARCHITECT
2. SEE STD. DET. No. 66 FOR ANCHORAGE
3. WALL THICKNESS REQUIRED TO BE DETERMINED BY DEBTH OF CABINET.
4. MAINTAIN, REQUIRED FIRE RATING OF WALL AROUND CABINET.



SECTION



PLAN

Veterans Administration STANDARD DETAIL 57

INTERIOR WALL BUMPER GUARDS

TITLE

DATE ISSUED JULY '77

REVISION

NOTES

7'-0" MIN.

THIS DIMENSION IS A MINIMUM RECOMMENDATION. THE COVERED AREA SHOULD BE DESIGNED IN RESPONSE TO THE SPECIFIC CONDITIONS OF EACH PROJECT: CLIMATE, ORIENTATION, SITE, ETC.

CANOPY OR BLDG. ABOVE

4'-0" MIN.



9'-6" (note #1) (see note #2)

10'-0" MIN. TO UNDERSIDE OF CANOPY OR BLDG. ABOVE.

22'-0" (note #1)

SECTION THRU UNLOADING AREA

NOTES

1. MINIMUM DIMENSION ALLOWED BY FED SPEC KKK-A-1822 "NATIONAL HIGHWAY TRAFFIC SAFETY ADMIN (NHTSA/DOT) 49 CFR 340 - FEDERAL MOTOR VEHICLE SAFETY STANDARDS FEDERAL HIGHWAY ADMIN (FHWA/DOT) 49 CFR 571 - MOTOR CARRIER SAFETY REGULATIONS.
2. INCLUDES ROOF MOUNTED EQUIPMENT, DOES NOT INCLUDE TWO-WAY RADIO ANTENNA.

7'-0"

20'-0" MIN. PREFERRED 24'-0"

DEPTH OF DOOR ACTIVATOR

AS REQ'D TO ACCOMODATE DOORS

7'-0"

20'-0" MIN. PREFERRED 24'-0"

DEPTH OF DOOR ACTIVATOR

TYP. ARRANGEMENTS

4'-0" MIN.

3'-0" MIN.

SEE NOTE ABOVE

7'-0" AREA FOR MANUVERING STRETCHER

CANOPY OR BLDG ABOVE

STRETCHER

8'-0" (note #1)

8'-0" LANE WIDTH / AMBULANCE

12'-0" LANE WIDTH / AMBULANCE + 4' MIN.

CANOPY OR BLDG ABOVE

DEPTH OF DOOR ACTIVATOR

DEPTH OF DOOR ACTIVATOR

WIDTH AS REQUIRED FOR DOOR(S)

EDGE OF BLDG. OR CURB

PLAN OF UNLOADING AREA

AMBULANCE ENTRANCE DETAILS FOR HEAD-IN OR DRIVE-THRU UNLOADING

TITLE

DATE ISSUED Sept. '79 | REVISION

58

Veterans Administration STANDARD DETAIL

TYP. ARRANGEMENTS



PLAN OF UNLOADING AREA



SECTION THRU UNLOADING AREA



Veterans Administration STANDARD DETAIL 59

AMBULANCE ENTRANCE DETAILS FOR BACK-IN UNLOADING

TITLE

DATE ISSUED Sept. '79 | REVISION

NOTES

1. MAXIMUM DIMENSION ALLOWED BY FED SPEC. KKK-A-1822 NATIONAL HIGHWAY TRAFFIC SAFETY ADMIN. (U.S/DOT.) 49 CFR 340 - FEDERAL MOTOR VEHICLE SAFETY STANDARDS FEDERAL HIGHWAY ADMIN. (US/DOT.) 49 CFR 571 - MOTOR CARRIER SAFETY REGULATIONS
2. INCLUDES ROOF MOUNTED EQUIPMENT; DOES NOT INCLUDE TWO-WAY RADIO ANTENNA.



FRONT ELEVATION



SECTION A-A



PLAN

Veterans Administration STANDARD DETAIL 60

SHELVING TYPES
4, 4A & 4B

TITLE

DATE ISSUED JUNE '76 | REVISION

NOTES

CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

ELEVATION



SECTION "A-A"



PLAN

SHELVING TYPE 6, 6A, 6B & 6E



FRONT ELEVATION



SECTION "B-B"



PLAN

SHELVING TYPE 6C

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

NOTE

1. WHERE TYPE 6, 6A, 6B & 6E UNITS OCCUR IN ROOMS DIRECTLY CONNECTED TO OPERATING ROOMS AND SCRUB UP AREA, THEY SHALL BE S/S WITH S/S SLOPING TOP AND VINYL BASE OVER S/S CHANNEL BASE.
2. TYPE 6C SHELVING IS FOR ETHER CAN STORAGE IN HYDRO CARBON GAS STORAGE ROOMS AND SHALL BE GROUNDED AS FOLLOWS. #10 WIRE BOLTED TO ONE OF REAR ANGLE POSTS AND ATTACHED TO NEAREST COLD WATER PIPE WITH APPROVED GROUND CLAMP. ALL METAL SHALL BE GALV. UNPAINTED.
3. WHERE TWO OR MORE UNITS ARE COMBINED THEY SHALL BE BOLTED TOGETHER AS SPECIFIED.
4. PROVIDE SINGLE METAL END BETWEEN UNITS AND METAL FILLER STRIP BETWEEN SHELF ENDS.
5. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

SHELVING, TYPES 6, 6A, 6B, 6C & 6E

60 B

JUNE '76



PLAN



ELEVATION



SECTION "A-A"

60A

Veterans Administration STANDARD DETAIL

SHELVING TYPE 5C

TITLE

DATE ISSUED DEC. '74

REVISION

NOTES

CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.







SHELVING TYPES 7 & 7B

DOORS WHEN REQUIRED IN EQUIPMENT GUIDE LIST HANDBOOK - H-08-5

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

SEE STANDARD DETAIL NO. 18 FOR SECURED STORAGE.



SHELVING TYPE 7A

NOTES

CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

TITLE: SHELVING TYPES 7, 7A & 7B

DATE ISSUED: APRIL 80

REVISION

60

Veterans Administration STANDARD DETAIL



ELEVATION
SINGLE UNIT

ELEVATION
MULTIPLE UNITS

SHELVING TYPE 7C (ABOVE COUNTERS OR WORK TOPS)



SINGLE SLOTTED E SHELF SUPPORTS

DOUBLE



TYPICAL ELEVATION
STORAGE ROOM SHELVING
TYPES 7D, 7E, 7F & 7G



DETAIL OF SHELF & BRACKET
SCALE: 3"=1'-0"

SHELVING TYPES 7C, 7D, 7E, 7F & 7G

60 D

DEC '74

NOTE:
PROVIDE 2 SHELF BRACKETS AT DOUBLE SLOTTED Es. BRACKETS & E SUPPORTS SHALL BE HEAVY DUTY TYPE.
SECURE E SUPPORTS TO WALL WITH ¼" TOGGLE OR EXP. BOLTS APPROX. 16" O.C.
NOTE TO DRAFTSMAN: FOR ANCHORAGE SEE STD. DETAIL Nº GG
USE SHELVING TYPE 7D OR 7G WHERE STORAGE SPACE IS REQUIRED BELOW SHELVING



ELEVATION SECTION

GENERAL SHELVING TYPES 37 & 37A



ELEVATION SECTION

BLANK FORM SHELVING
TYPE 38



ELEVATION

SHELVING TYPE 37B
(MEDICAL STORAGE)
SHELVES APPROX. 12½" DEEP



ELEVATION SECTION

BAGGAGE SHELVING TYPE 35

NOTE: 2'-0" UNITS OF TYPE 35 MAY BE USED WHERE REQUIRED.

NOTE:
METAL BACKS AND ENDS OF SHELVING TYPES 35, 37, 37A, 37B AND 38 SHALL EXTEND TO FLOOR.
CONTRACTOR SHALL PROVIDE LARGE SCALE SHOP DRAWINGS.
WHERE SHELVING UNITS ARE ADJACENT TO EACH OTHER OR BACK TO BACK, THEY SHALL BE BOLTED TOGETHER.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL AND FLOOR SEE STANDARD DETAIL NO. 66.

NOTES

SHELVING TYPES
35, 37, 37A, 37B & 38

TITLE

DATE ISSUED APRIL 80 | REVISION

60E
Veterans Administration
STANDARD DETAIL



END ELEV. TYPE 41M & 41P

ELEVATION TYPES 41M, 41MM, 41P & 41PP



END ELEV. TYPE 41MM & 41PP

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66



PLAN - TYPE 41M & 41P



PLAN - TYPE 41MM & 41PP

NOTE ON FREE STANDING UNITS BOLT TO FLOOR WITH 1/4" BOLTS. FOUR BOLTS PER UNIT.

NOTE:
PROVIDE LABEL HOLDERS AT FRONT EDGE OF SHELVES.
ALL SHELVING UNITS SHALL BE SECURED TOGETHER.
END PANEL NOT REQUIRED WHERE END UNIT ABUTS WALL.
CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

SHELVING, LIBRARY, TYPES 41M, 41MM, 41P & 41PP

60 F

DEC. '74



END ELEV.
TYPE 43M

ELEVATION
TYPES 43M & 43MM



END ELEV.
TYPE 43MM

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66



PLAN - TYPE 43M



PLAN - TYPE 43MM

NOTE: ON FREESTANDING UNITS, BOLT TO FLOOR WITH 1/4" BOLTS. FOUR BOLTS PER UNIT.

NOTE:
PROVIDE LABEL HOLDERS AT FRONT EDGE OF SHELVES.
ALL SHELVING UNITS SHALL BE SECURED TOGETHER.
END PANEL NOT REQUIRED WHERE END UNIT ABUTS WALL.
CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

SHELVING, LIBRARY, TYPES 43M & 43MM

(PERIODICAL SHELVING)

DEC. '74

60 G

VA ARCHITECTURAL STANDARD DETAIL



PART ELEVATION
OF SHELF TYPE 44



SECTION "A-A"

NOTE:
SEE ARCHITECTURAL PLANS
FOR LENGTH OF SHELF.

SHELF TYPE 44



ELEVATION

SECTION "A-A"

SHELVES TYPES 45 AND 45C

NOTE:
SEE ARCHITECTURAL PLANS FOR LOCATION OF STAINLESS STEEL SHELVES TYPES 44, 45 AND 45C.
TOP OF SHELF TYPE 45C SHALL BE LOCATED 1'-5" ABOVE RIM OF UTILITY SINK.
WHERE SHELF TYPE 45C OCCURS ABOVE FLUSHING RIM SERVICE SINK IT SHALL CLEAR FITTING SUPPORT A MINIMUM OF 2".
SEE ARCHITECTURAL PLANS FOR EXTENT OF SHELVING AND ACTUAL SPACING OF BRACKETS.

SHELVING, TYPES 44, 45, AND 45C

DEC'. 74

60 H

VA ARCHITECTURAL STANDARD DETAIL



FRONT ELEVATION

SECTION



END ELEVATION OF LOCKERS BACK TO BACK



PLAN OF WALL LOCKERS (TWO TIER TYPE C (LOCKERS))

END ELEVATION



TYPICAL CORNER RETURN

LOCKER TYPE	SIZE
B	1'-0" X 1'-9" X 6'-0"
C	1'-3" X 1'-6" X 3'-0"

NOTES:

1. ATTACH VINYL BASE OVER METAL FILLER PLATES.
2. CONTRACTOR SHALL PROVIDE SHOP DRAWING DETAILS.
3. EACH LOCKER SHALL BE EQUIPPED WITH A SHELF AND THREE COAT HOOKS.

LOCKERS - METAL TYPES B&C

JAN.'61

61

JULY 71

VA ARCHITECTURAL STANDARD DETAIL



FRONT ELEVATION

SECTION "A-A"



PLAN

NOTE:
SEE PLANS FOR NUMBER OF WARDROBE LOCKERS.
DOORS SHALL BE RIGHT OR LEFT HAND, SEE PLANS.
CONTRACTOR SHALL PROVIDE SHOP DWG. DETAILS.

DETAILS SHOWN IN METAL STUD AND PLASTER OR DRYWALL PARTITIONS. REVISE AS NECESSARY FOR INSTALLATION IN OTHER TYPES OF PARTITIONS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE SEE STANDARD DETAIL NO. CC

LOCKERS WARDROBE TYPE S-3
(BUILT-IN)

JULY '77

61
A

VA. ARCHITECTURAL STANDARD DETAIL



SECTION - 'A-A'



JAMB SECTION - 'B-B'
(NON-FIRE RATED WINDOW)



JAMB SECTION - 'C-C'
FIRE RATED WINDOW
1 1/2 HOUR, B-LABEL



ELEVATION

NOTES

1. DETAILS OF PASS WINDOW SHALL INDICATE THE TYPE OF PARTITION(S) IN WHICH THEY OCCUR. LINTELS SHALL BE PROVIDED AS NECESSARY. PROPER DIMENSIONS SHALL BE GIVEN.
2. PASS WINDOW IN 2 HOUR FIRE RATED WALLS SHALL HAVE A 1 1/2 HOUR (B LABEL) RATING AND SHALL BE EQUIPPED TO CLOSE BY AUTOMATIC FUSIBLE LINK. ARCHITECT SHALL NOTE ON PLANS WHICH PASS WINDOWS ARE TO BE FIRE RATED.
3. CORNERS TO BE BENT OR WELDED AND GROUND SMOOTH WITH SLIGHT RADIUS PROVIDED.

PASS WINDOW DETAILS
(PRE-ASSEMBLED)

TITLE

DATE ISSUED JAN. '79 | REVISION

62

Veterans Administration STANDARD DETAIL



SECTION

ELEVATION



Veterans Administration STANDARD DETAIL 64

RECESSED SPECIMEN PASS BOX

TITLE

DATE ISSUED JAN. '81

REVISION

NOTES

1. ENTIRE UNIT FABRICATED OF 18 GAUGE STAINLESS STEEL.

2. SELF CLOSING DOORS WITH LOCKING MECHANISM TO PREVENT BOTH DOORS FROM BEING OPENED AT SAME TIME.



ELEVATION
scale 3/4": 1'-0"



AT CHANNEL ANCHORAGE (SEE STANDARD DETAIL #66)

MOP (N.I.C.)

SECTION
scale 3/4": 1'-0"

NOTES

MOP RACK TYPE 10

TITLE

DATE ISSUED 6/7/82

REVISION

64 B

Veterans Administration STANDARD DETAIL



ELEVATION.



SECTION A-A
(ON CONCRETE OR SOLID MASONRY WALL)



SECTION A-A
(DRYWALL ON METAL STUD PARTITION)



SECTION AT BASE
METAL STUD PARTITION

CHAIN RACK FOR GAS STORAGE.



PART ELEVATION



1/2 F.S. DETAIL "B"

PART PLAN



SECTION.

NOTE:

1. CYLINDER RACKS SHALL BE GROUNDED AS FOLLOWS: PROVIDE #10 COPPER WIRE EXTENDED TO NEAREST COLD WATER PIPE AND CONNECTED TO APPROVED GROUND CLAMPS ATTACHED TO PIPE FRAME AT REAR OF RACK AND TO COLD WATER PIPE.
2. WHERE CHAIN RACK OCCURS ON C.M.U. PARTITION FILL CELLS SOLID WITH CONCRETE OR PROVIDE SOLID MASONRY FOR THRU BOLTS.
3. HOOKS & EYES OF CHAIN RACKS TO EXTEND THRU 2"X1/2" METAL BAR AND WELD FLUSH ON BACK. METAL BAR SHALL BE GROUNDED AS FOLLOWS: PROVIDE #10 WIRE BOLTED TO METAL BAR AND ATTACHED TO NEAREST COLD WATER PIPE WITH APPROVED GROUND CLAMP.
4. ALL METAL OF CYLINDER RACKS AND CHAIN RACKS SHALL BE GALVANIZED AND LEFT UNPAINTED.
5. SEE PLANS FOR OVERALL LENGTH OF RACKS.

NOTES

TITLE: GAS STORAGE RACK

DATE ISSUED Sept. '79 | REVISION

Veterans Administration STANDARD DETAIL

ELEVATION SECTION

TYPE 3 (MOVABLE)



ELEVATION SECTION

TYPE - 2



PLAN

TYPE - 3



PLAN

TYPE - 2

NOTE:
ALL SHELVES & DIVIDERS IN BINS TYPES 2 & 3 SHALL BE FIXED.
METAL DIVIDERS SHALL BE FLANGED AT TOP, BOTTOM & BACK.
FRONT EDGES OF DIVIDERS SHALL BE BEADED.
CONTRACTOR SHALL PROVIDE SHOP DWGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

BINS, CLOTHING - TYPES 2 & 3

DEC '74

65



ELEVATION



SECTION



PLAN

NOTE:

1. FRONT EDGE OF ALL DIVIDERS SHALL BE BEADED.
2. DIVIDERS SHALL BE ADJUSTABLE AT 2" INTERVALS.
3. PROVIDE A CONTINUOUS LABEL HOLDER STRIP AT FRONT EDGE OF EACH SHELF.
4. CONTRACTOR SHALL PROVIDE SHOP DWGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

BINS, TYPE 3A

65A

3.74

VA ARCHITECTURAL STANDARD DETAIL



SECTION THRU UNIT



ELEVATION OF UNIT



PLAN DETAIL



PLAN OF UNIT

NOTE: ON FREE STANDING UNITS, BOLT TO FLOOR WITH ¼" BOLTS. FOUR BOLTS PER UNIT.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

BINS, X-RAY FILM STORAGE TYPE 9

JAN. '81

65B

DEC. '74



TYPICAL CASEWORK AND/OR EQUIPMENT ELEVATIONS SHOWING HAT CHANNEL LOCATIONS ON MET. STUD PARTITIONS



SECTION THRU METAL STUD PARTITION AND WALL MOUNTED ITEM



DETAIL OF ANCHORAGE OF HAT CHANNEL (FOR ALL WALL MOUNTED ITEMS NOT REQUIRING SPECIAL ANCHORAGE)



SECTION SHOWING WALL MOUNTED ITEMS HUNG ON SOLID MASONRY

NOTES:
1. CONTRACTOR SHALL DETERMINE THE LOCATIONS, HEIGHT & LENGTH OF HAT CHANNELS REQUIRED FROM THE EQUIPMENT MFGR. SHOP DRAWINGS PRIOR TO INSTALLING HAT CHANNELS.
2. TWO BOLTS TOP & BOTTOM PER UNIT MINIMUM. BOLTS 2'-0"-O.C. MAXIMUM. BOLTS TO BE LOCATED WITHIN 6" OF EACH END OF EQUIPMENT.
3. IF MFGRS STD. ITEM HAS NO REAR CORNER PROJECTION THEN NO FILLER CLOSURES OR HAT CHANNELS BETWEEN BACK OF CABINET AND WALL FINISH ARE REQUIRED.



DETAIL "A"

ANCHORAGE FOR WALL MOUNTED ITEMS
(NOT REQUIRING SPECIAL ANCHORAGE)

JULY '77

VA # ARCHITECTURAL DETAIL



PLAN

1" = 1'-0"



HEAD DETAIL (A)

3" = 1'-0"



JAMB DETAIL (B)

3" = 1'-0"



ELEVATION

1/2" = 1'-0"



SILL (SHELF) DETAIL (C)

3" = 1'-0"

NOTES

1. NUMBER & ARRANGEMENT OF WINDOWS SHOULD BE DESIGNED FOR INDIVIDUAL PROJECTS.
2. FIRE SHUTTER W/FUSIBLE LINK & SMOKE DETECTOR (SEE STANDARD DETAIL 62 (SIM)) IS REQUIRED TO BE ADDED WHEN SERVICE WINDOWS ARE LOCATED IN A FIRE RATED WALL.

SERVICE WINDOWS FOR CREDIT UNION AND AGENT CASHIER

TITLE

DATE ISSUED 1/31/89 | REVISION

67

Veterans Administration STANDARD DETAIL

Veterans Administration STANDARD DETAIL

67A

PASS-THRU, WALL OPENING BETWEEN CASHIER'S OFFICE AND TRAVEL OFFICE

TITLE

DATE ISSUED Sept. '79 | REVISION

NOTES



PLAN



SECTION "E-E"



SECTION "A-A"

SECTION "B-B"



ELEVATION OF WHEEL CHAIR HGT. WINDOW (FROM PATIENTS SIDE)



ELEVATION OF STANDARD HEIGHT WINDOWS (FROM PATIENTS SIDE)



DETAIL "1"



SECT. "F-F"



SECTION "C-C"



SECTION "D-D"

NOTES

1. NUMBER AND ARRANGEMENT OF WINDOWS AND BOX SHOULD BE DESIGNED FOR INDIVIDUAL PROJECTS.
2. FIRE SHUTTER W/FUSIBLE LINK AND SMOKE DETECTOR (SEE STD. DET. 62 SIMILAR) IS REQUIRED TO BE ADDED WHEN WINDOWS ARE LOCATED IN A FIRE RATED WALL.
3. REVISE DETAIL AS NECESSARY FOR METAL STUD AND PLAS. FINISH OR MAS. BLOCK AND PLAS. FINISH.

TITLE: SERVICE WINDOW AND PACKAGE TRANSFER BOX FOR PHARMACY

DATE ISSUED: 9/30/20

REVISION

67B

Veterans Administration STANDARD DETAIL



DETAIL "A"

BASIC METHOD FOR BRACING AGAINST UP-LIFT

ORAL METHOD FOR BRACING AGAINST UP-LIFT

Veterans Administration STANDARD DETAIL 68

CEILING BRACING FOR SEISMIC FORCES FOR USE WITH ACOUSTICAL TILE LAY IN CEILING

TITLE

DATE ISSUED JAN. '79

REVISION

NOTES

1. IN SPACES 12 FT x 12 FT OR LESS IN BOTH DIRECTIONS ONLY ONE VERTICAL STRUT IS REQUIRED
2. DO NOT ANCHOR RUNNER TEES OR CROSS TEES TO WALL ANGLE.
3. ALL WIRE SHALL BE TAUT WITH 3 COMPLETE TURNS AROUND SELF.
4. DRILL ONE WALL OF 3/4" CONDUIT PRIOR TO ERECTION TO ACT AS A PILOT HOLE FOR THRU-DRILLING WHEN BOTH CONDUITS ARE FIRMLY HELD IN PLACE.



WALL ELEVATION



TYPICAL WALL PLAN



PLAN OF WALL WITH DOOR



DETAIL "B"

NOTE: ADDITIONAL REINFORCING BARS ARE REQUIRED AROUND OPENINGS, AT CORNERS, ANCHORED INTERSECTIONS IN WALL PIERS AND AT END OF WALL PANELS SUCH AS AT CONTROL JOINTS.

NOTE

SEE V. A. SEISMIC HANDBOOK H-08-8 FOR SIZE & SPACING OF ALL HORIZONTAL & VERTICAL STEEL BARS



SECTION "A-A"

68A

REINFORCED MASONRY PARTITIONS (FOR SEISMIC FORCES)

JUNE '75

VA ARCHITECTURAL STANDARD DETAIL



PLAN 4&5 BEDROOM UNIT
TYPE S-2

PLAN 1&2 BEDROOM UNIT
TYPE S-1



ELEV. BEDROOM SIDE
1&2 BEDROOM UNIT
TYPE S-1

ELEV. BEDROOM SIDE
4&5 BEDROOM UNIT
TYPE S-2



ELEV. CORRIDOR SIDE
4&5 BEDROOM UNIT
TYPE S-2

ELEV. CORRIDOR SIDE
1&2 BEDROOM UNIT
TYPE S-1

NOTE:
DOORS SHALL BE RIGHT OR LEFT HAND SEE PLANS.
SEE DRAWING NO. 70A FOR DETAILS.
SEE MECHANICAL DRAWINGS AND SPECIFICATIONS FOR CONNECTIONS FROM VENTS TO EXHAUST SYSTEM.

NOTE TO ARCHITECT:-
THESE NURSE SERVER UNITS SHALL BE USED AS DESIGNED ONLY IN FULLY SPRINKLERED AREAS OF BUILDINGS WHERE RATED CORRIDOR PARTITIONS ARE NOT REQUIRED.



SECTION A A

CABINETS, NURSE SERVER TYPES S1 & S2

70

APRIL '78



SECT. 5-5

SECT. 6-6
(SECT. 7-7 AS NOTED)



SECT. 3-3



SECT. 4-4



SECT. 1-1



SECT. 2-2
SHOWING TYPICAL FRONT & REAR EDGE OF ADJUSTABLE SHELVES

NOTE:

1. ALL SECTIONS SHOWN APPLY EITHER RIGHT OR LEFT HAND.
2. REINFORCE FOR HARDWARE WHERE REQUIRED.
3. REFER TO SPECIFICATIONS FOR METAL GAGES.
4. TOTE TRAYS WILL BE SUPPLIED BY VETERANS ADMINISTRATION.
5. NURSE SERVER MANUFACTURER SHALL LOCATE TOTE TRAY SUPPORTS IN ACCORDANCE WITH TOTE TRAY MANUFACTURER'S TEMPLATE.
6. SEE SECT. A-A ON STANDARD DETAIL # 70

CABINETS, NURSE SERVER TYPES S-1 & S-2, DETAILS

70A



ELEVATION

SECTION "A-A"



PLAN

CABINET ASSEMBLY TYPE IA
(BASE CABINET IA/B)
(WALL CABINET IA/W)

CABINET IA/W

CABINET IB/W

CABINET IA/B

CABINET IB/B



ELEVATION

SECTION "A-A"



PLAN

SINK IN CABINETS IN OCCUPATIONAL THERAPY CLINICS TO HAVE REMOVABLE STRAINERS.

CABINET ASSEMBLY TYPE IB
(BASE CABINET IB/B)
(WALL CABINET IB/W)

NOTES:

1. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

CABINET ASSEMBLY TYPES IA & IB

70B

JUNE '78



ELEVATION



CABINET IG/W

CABINET IG/B

SECTION



PLAN

(BASE CABINET IG/B)
(WALL CABINET IG/W)

NOTE: CONTRACTOR SHALL PROVIDE SHOP DWGS.

REVISED 6/82

CABINET ASSEMBLY TYPE IG

70C

MAR-H'78



ELEVATION
(WITH DOORS REMOVED)



SECTION "A-A"



SECTION "B-B"



PLAN C-C



ELEV. OF
SLIDING DOORS



PLAN "D-D"

NOTE: PROVIDE RESILIENT BUMPERS IN JAMB FRAMES TO INSURE QUIET OPERATION OF SLIDING DOORS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

NOTES
1. SEE ARCHITECTURAL PLANS FOR ACTUAL ARRANGEMENT.
2. CONTRACTOR TO PROVIDE SHOP DRAWINGS.

CABINET TYPE 5A (WARDROBE)

70D

JUNE '76



ELEVATION



SECTION "A-A"



PLAN

NOTE:
CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

CABINET TYPE 5B

DEC' 74

70 E



ELEVATION



SECTION



PLAN



NOTE: CONSTRUCTION SHALL BE OF WELDED ASSEMBLY.
PAINT THE FOLLOWING LETTERING ON DOORS: "SURGICAL GAS SUPPLY UNIT FOR OXIDIZING AND INERT GASES ONLY. KEEP LIGHTS AND FIRES AWAY."
CABINET SHALL BE GROUNDED SIMILAR TO SHELVING TYPE 6C. SEE SHEET 60B.
THIS CABINET TO BE USED WHERE REQUIRED IN ALTERATION PROJECTS ONLY.
FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

CABINET TYPE 6D
(OXIDIZING GAS SUPPLY)

DEC' 74

70F





ELEVATION OF WOOD LINING AT BACK OF CABINET

NOTE:
CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

CABINET TYPE 8-A (TOOL) 70G

JAN. 76

VA ARCHITECTURAL STANDARD DETAIL



NOTE: SEE STD. DET. NO. 70G FOR TYPE 8A CABINET.

FOR ANCHORAGE TO WALL, SEE STD. DETAIL NO 66

THE CONTRACTOR SHALL PROVIDE SHOP DWGS.



CABINETS TYPES 8, 8B & 8C

70H

VA ARCHITECTURAL SYMBOLS DETAIL



PLAN



DETAIL OF HANGER PIN

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.
MASONRY CONSTRUCTION IS SHOWN ON THIS DETAIL, HOWEVER METAL STUD CONSTRUCTION MAY BE USED.



PLAN



SECTION A-A



ELEVATION



SECTION



ELEVATION AT CENTER OF DOUBLE CABINET

CABINET TYPE II-A (WITHIN OPERATING ROOMS)



ELEVATION



SECTION

CABINET TYPE II-A (OUTSIDE OF OPERATING ROOMS)

CABINET TYPE IIA (INSTRUMENT)

(FOR ALTERATION PROJECTS ONLY)

DEC 74

70J

NOTES:
1. CABINET TYPE IIA NOT REQUIRED IN NEW HOSPITAL BUILDINGS
2. WHERE CABINET TYPE IIA OCCURS WITHIN OPERATING SUITE, IT SHALL BE OF S/S CHANNEL BASE AND S/S SLOPING TOP.
3. CONTRACTOR SHALL PROVIDE SHOP DWGS.



ELEVATION SECTION



ELEVATION SECTION



PLAN (4'-0" UNIT)

NOTE:
4'-0" UNITS ARE TYPICAL FOR TYPE 13.
3'-0" OR 2'-0" UNITS MAY BE USED WHERE REQUIRED (SEE PLANS)



PLAN (2'-0" UNIT)



PLAN

CABINET TYPE 13

CABINET TYPE 14

NOTE:
WHERE CABINET TYPE 13 OCCURS IN DIETETIC SERVICE IT SHALL BE S/S, 3'-0" WIDE, WITH S/S SHELVES, S/S SLOPING TOP AND VINYL OVER S/S CHANNEL BASE. CONTRACTOR SHALL PROVIDE SHOP DWGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

CABINETS TYPES 13 & 14

DEC. '74

70 K



ELEVATION

SECTION



PLAN

NOTE:
FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

WHERE THIS CABINET OCCURS WITHIN OPERATING SUITE, IT SHALL BE OF S/S WITH VINYL BASE OVER S/S BASE.

CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.

CABINET TYPE 14A

DEC' 74

70 L



ELEVATION

SECTION



PLAN

CABINET ASSEMBLY TYPE 17
(BASE CABINET 17/B)
(WALL CABINET 17/W)

NOTE: CONTRACTOR SHALL PROVIDE SHOP DWGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

CABINET ASSEMBLY TYPE 17

JULY '77

70M



ELEVATION



SECTION



PLAN



LIGHTING UNIT = FLUOR. SHOWCASE REFLECTOR WITH MECH. LAMP EJECTOR AND REMOTE BALLAST.

LIGHTING DETAIL "A"

NOTE:
FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.
GLASS SHELVES OF CABINET TYPE 25 SHALL BE SUPPORTED AT ENDS ON BRACKETS AND SHALL CLEAR FLUORESCENT LIGHTING.
PROVIDE LOCKS ON DOORS OF EACH UNIT OF CABINET TYPE 25.
CONTRACTOR SHALL PROVIDE SHOP DWGS.

CABINET, DISPLAY, TYPE 25

70 N

DEC '74



36" CABINET (SIZE 1)

48" CABINET (SIZE 2)



TYPICAL SECTION



60" CABINET (SIZE 3)



72" CABINET (SIZE 4)

NOTES TO ARCHITECT

1. SEE STANDARD DETAIL NO. 71 FOR DETAIL OF CLEARANCE FOR RECESSED CABINETS.
2. SEE EQUIPMENT GUIDE LIST FOR SIZES OF MEDICINE CABINET(S) TO BE USED.
3. CALL FOR CLOSED ENDS WHEN CABINET IS NOT RECESSED.
4. NOTE TO ELECTRICAL DESIGNER (ARCHITECT COORDINATE): PROVIDE TWO SEPARATE 120 V, 20A, 1Ø CIRCUITS FOR MEDICATION CABINET.

MEDICINE CABINETS TYPE 18C (SIZES 1, 2, 3, & 4)

70 P

(REPRODUCTION SAMPLE NOT REQUIRED)

MARCH '78



NOTES :-

1. ALL EXPOSED EXTERIOR SURFACES TO BE WOOD GRAIN PLASTIC LAMINATE.
2. BRASS DOOR PULLS AND HINGES.
3. USE 3/4" PARTICLE BOARD OR PLYWOOD THROUGHOUT.
4. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS OF LARGE SCALE DETAILS SHOWING CONSTRUCTION & JOINTING.
5. BOLT TO WALL, PER STD. DETAIL NO. 66.

70 Q

DISPLAY CABINET TYPE 25A

JUNE '78

JAN. 81

JA ARCHITECTURAL STANDARD DETAIL



A ELEVATION



SECTION "A-A"



PLAN



PART PLAN OF RECESSED CABINET

NOTE:
CABINET "TYPE 22 MODIFIED" SHALL HAVE OVEN IN LIEU OF UTENSIL DRAWER AND UTILITY CABINET

NOTE:
LIGHT FIXTURE, 20 WATT FLUORESCENT, WITH 22GA. BAKED ENAMEL STEEL REFLECTOR WITH CLOSED ENDS AND TRIGGER STARTING TYPE BALLAST. FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO.66.

KITCHEN CABINET TYPE 22 & 22 MODIFIED

JUNE '76

71

VA ARCHITECTURAL STANDARD DETAIL

JAN. 81

NOTE: WHEN CEILING IS FURRED DOWN TO CABINET TOP, PROVIDE VENTILATING GRILLE IN FURRED SPACE ABOVE CABINET.



NOTE FOR CABINET TYPE 22-E:
OTHER ARRANGEMENT OF PARTS OF CABINET WILL BE ACCEPTABLE PROVIDING ALL SPECIFIED COMPONENTS ARE INCLUDED.



KITCHEN CABINET TYPE 22-E





KITCHEN CABINET TYPE 22-C

NOTE: CONTRACTOR SHALL PROVIDE SHOP DWGS.

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

KITCHEN CABINETS TYPES 22-C & 22-E

71 A

JULY '77



ELEVATION



SECTION



PLAN

NOTE: CONTRACTOR SHALL PROVIDE SHOP DWGS.

FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

KITCHEN CABINET TYPE 22F

71C





PLAN

BASE CABINET 22G/B
WALL CABINET 22G/W

CONTRACTOR SHALL PROVIDE SHOP DWGS.

FOR ANCHORAGE SEE STD. DETAIL NO. 66

KITCHEN CABINET ASSEMBLY TYPE 22G

71D



DETAIL NO-1 DETAIL NO-2



ELEVATION



SECTION



PLAN

NOTE TO DRAFTSMAN: FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66

COUNTER, DRESSING (MAKE-UP) TYPE B

72A

NOTE: NUMBER OF INDIVIDUAL COUNTERS SHALL BE AS SHOWN ON FLOOR PLANS.

JUNE '75

JAN. 81

VA ARCHITECTURAL STANDARD DETAIL



ELEVATION SECTION



ELEVATION



PLAN

COUNTER TYPE IF



SECTION



ELEVATION



SECTION

COUNTER TYPE IL

NOTES:

1. COUNTERS CAN BE RIGHT OR LEFT HAND SEE PLANS.
2. CONTRACTOR SHALL PROVIDE SHOP DWG.
3. FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO.66.



PLAN

COUNTER TYPE IK

COUNTERS TYPES IF, IK & IL

72C

JULY '77



ELEVATION



SECTION "A-A"



SECTION "B-B"

NOTE:
THIS DRAWING SHOWS A COMPOSITE ARRANGEMENT OF THE VARIOUS TYPES OF METAL CASEWORK UNITS REQUIRED UNDER THE WOOD COUNTER TOP. ACTUAL NUMBER AND ARRANGEMENT OF UNITS SHALL BE DETERMINED BY D.M.&S. FOR EACH PROJECT.
CONTRACTOR SHALL PROVIDE A SHOP DWG.

COUNTER-- WORK BENCH TYPE 1M

72D

JULY '77

JA



ELEVATION





SECTION "A-A"

SECTION "B-B"

NOTE:
THIS DRAWING SHOWS A COMPOSITE ARRANGEMENT OF THE VARIOUS TYPES OF METAL CASEWORK UNITS REQUIRED UNDER THE WOOD COUNTER TOP. ACTUAL NUMBER AND ARRANGEMENT OF UNITS SHALL BE DETERMINED BY D.M.&S. FOR EACH PROJECT.
CONTRACTOR SHALL PROVIDE A SHOP DWG.

COUNTER-- WORK BENCH TYPE IM

72D

JULY '77

JA



ELEVATION



SECTION "A-A"



SECTION "B-B"

NOTE:

CONTRACTOR SHALL PROVIDE SHOP DWGS.

FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

COUNTERS TYPES 15 & 15A

JULY

72E



ELEVATION

COUNTER TYPE 15B



SECTION "A-A"

SECTION "B-B"



ELEVATION

COUNTER TYPE 15D

NOTES:

1. COUNTER TYPE 15D MAY BE RIGHT OR LEFT HAND AS DETERMINED BY PLANS
2. CONTRACTOR SHALL PROVIDE SHOP DWGS.



ELEVATION

COUNTERS TYPES 15E & 15F



SECTION THRU
COUNTER TOP AND
BACKSPLASH-ALL COUNTERS

COUNTERS TYPES 15B,15D,15E & 15F

72F

VA ARCHITECTURAL STANDARD DETAIL JAN. 81



COUNTER TYPE 16



COUNTER TYPE 16B



COUNTER TYPE 16 A

NOTES:

1. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS.
2. FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.

COUNTER TYPES 16, 16A, & 16B

REVISED 6/82
JAN. '76

72G





½ PLAN

COUNTER TYPE 23





PLAN

COUNTER TYPE 28

NOTES:

1. COUNTER TYPE 28 SHALL BE S/S CONSTRUCTION.
2. FOR ANCHORAGE TO WALL, SEE STANDARD DETAIL NO. 66.
3. PROVIDE CLOSED FINISHED ENDS IF NOT LOCATED AGAINST SIDEWALL.
4. CONTRACTOR SHALL PROVIDE SHOP DWGS.

COUNTERS TYPES 23 & 28

72H

MARCH '78



BASE SECTION

NOTES TO DRAFTSMAN

DETAIL SHOWN IS FOR USE W/ METAL STUD AND GYPSUMBOARD PARTITION FINAL DETAILS DRAWN SHALL REFLECT CONDITIONS AS THEY EXIST FOR EACH SPECIFIC INSTALLATION.

COUNTERS, THRU-WALL

72-K

INTERIM COPY
JULY '77
JAN. 81

VA ARCHITECTURAL STANDARD DETAIL